

ARTICLE XVIII - ASPHALT CONCRETE PAVEMENT

18.1 DESCRIPTION

This work shall consist of constructing asphalt concrete pavement on a prepared base course, including cold-planing and overlaying asphalt concrete pavement on an existing base surface, in accordance with the requirements of the contract.

18.2 GENERAL REQUIREMENTS

The provisions of Section 401 – Hot Mix Asphalt (HMA) Pavement of the "Standard Specifications" shall apply except as hereinafter modified:

(A) 401.03 (A) Construction Requirements shall be amended to read as follows:

Amend (A) Weather Limitations to read as follows:

"(A) Weather Limitations. Do not place the bituminous plant mix:

- (1) on wet surfaces, or
- (2) when the air temperature is below 50°F., or
- (3) when weather conditions prevent the proper handling or finishing of the bituminous mixtures."

The Contractor shall notify the construction engineer, in writing, if concrete is to be furnished by a ready-mix supplier. The Contractor shall submit Delivery/Batch Ticket Documentation to the construction engineer when the ready-mix concrete is poured and no later than when the truck leaves the work area in which the concrete was poured.

(B) 401.04 Measurement and 401.05 Payment are deleted.

18.3 MEASUREMENT AND PAYMENT

Asphalt concrete pavement, within the pavement stabilization boundary, including bituminous aggregate material, tack coat, and prime coat, will be paid for on a lump sum basis in the Proposal Schedule, complete in place.

Payment shall be full compensation for all tools, material, labor, and appurtenances to complete the work, in accordance with the construction documents, in place, complete.

Asphalt concrete pavement for trench restoration will be paid for under Article XV – Trench Excavation and Backfill.

ITEM NO.	PAY ITEM	PAY UNIT
14.	Asphalt concrete pavement, State Mix IV, in place, complete.	Lump Sum

END OF ARTICLE

S70156

18-1