

ARTICLE XXII - TRAFFIC CONTROL

22.1 GENERAL

In general, the applicable provisions of Section 645 – Work Zone Traffic Control of the "Standard Specifications" shall apply except as hereinafter modified:

- (A) The Contractor shall submit a detailed Traffic Control Plan to the Construction Engineer for approval at least 15 days before work on that phase commences. All items as specified in Section 645.03 shall be provided. Additional items shall include the location and installation of gate(s) in the container yard fencing for construction access, and the location and marking of all barriers and temporary fencing for the Construction Storage and Staging area.
- (B) Traffic Plates. Skid resistant plates shall be used. Plates shall be rated and secured to permit the safe passage of all container yard traffic under maximum load conditions, including top pick and Fantuzzi carriers, forklifts, and semi-trailers.
- (C) The Contractor shall remove all concrete barriers, temporary signs, temporary striping, and all other Contractor-owned temporary traffic control devices off of the State Department of Transportation, Harbors Division's property after construction is complete.

22.2 PAYMENT

Traffic controls, including traffic control plan, phasing, materials, tools, labor, and incidentals to complete the work will not be measured or paid for separately, but shall be considered incidental to the various items of work in the Proposal Schedule.

END OF ARTICLE