

SECTION 702 - BITUMINOUS MATERIAL

Make the following amendments to said Section:

(I) Amend **702.01 Asphalt Cement** to read as follows:

"702.01 Asphalt Cement. Performance graded asphalt binder shall conform to AASHTO Provisional Standard MP1."

(Table deleted.)

(II) Amend **702.04 Emulsified Asphalts** to read as follows:

"702.04 Emulsified Asphalt. Anionic emulsified asphalt shall conform to AASHTO M 140, except that the penetration on residue for Type SS-1 and Type RS-1 shall be 50-120 in lieu of the 100-200 specified.

Cationic emulsified asphalt shall conform to AASHTO M 208, except that the penetration on residue for Type CSS-1 and Type CRS-2 shall be 50-150 in lieu of the 100-250 specified."

END OF SECTION