

GENERAL NOTES

| FED. ROAD DIST. NO. | STATE | FED. AID PROJ. NO. | FISCAL YEAR | SHEET NO. | TOTAL SHEETS |
|---------------------|-------|--------------------|-------------|-----------|--------------|
| HAWAII | HAW. | STP-0700(38) | 1998 | 3 | 29 |

1. The scope of work for this project includes constructing paved shoulders; removing and installing metal guardrail; installing pavement markings and markers; installing signs; and trimming and dressing of shoulders.
2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3. The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 - Public Convenience and Safety, Subsection 107.21 - Contractor's Responsibility for Utility Property and Services, Section 645 - Traffic Control.
4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6. The exact locations and limits or areas to be excavated and reconstructed shall be determined in the field by the Engineer.
7. The Contractor shall notify the State in writing, two (2) weeks prior to starting paving operations.
8. Smooth riding connections shall be constructed at all limits of resurfacing including the beginning and end of project, connecting approaches, side streets and driveways as shown on the plans and/or as directed by the Engineer.
9. Dressing of shoulder shall consist of clearing, grubbing, grading, reshaping and compacting the unpaved shoulders with suitable excavated material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.
10. Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to the various contract items.
11. Earth swale shall be graded to drain. This work shall be considered incidental to the various contract items.
12. Contractor shall provide for access to and from all existing side streets at all times.
13. All saw cutting work shall be considered incidental to Roadway Excavation.
14. Type C Flare terminal ends, complete, in place; Type F Flare terminal ends, complete, in place, and Type G terminal ends, complete, in place shall not be paid for separately, but shall be included under Item No. 606.3230 - GUARDRAIL, TYPE 3, SINGLE, WITH SPACER ON STEEL POST.

SRT-350 Terminal Ends, complete, in place, shall be paid for separately under Item No. 606.7001, TERMINAL SECTION, TYPE SRT-350.

LEGEND

- °pp Existing Power Pole
- e— Existing Electrical Line
- s— Existing Sewer Line
- s— Existing HTCO Line
- w—12" Existing Water Line
- °wv Existing Water Valve
- wv Existing Water Valve to be Adjusted
- ✧fh Existing Fire Hydrant
- °av Existing Water Air Valve
- gdi Existing Grated Drop Inlet
- GDI New Grated Drop Inlet
- Existing Utility Box

| | | |
|---------------|------------------------|------|
| ORIGINAL PLAN | SURVEY PLATTED BY | DATE |
| NOTED BOOK | DRAWN BY S. Markawa | X |
| 004, Jason | DESIGNED BY S. Markawa | |
| 004, Jason | CHECKED BY | |
| 004, Jason | CHECKED BY | |

| | |
|--|------------------|
| STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION | |
| GENERAL NOTES AND LEGEND | |
| <u>RICE STREET, KUHIO HIGHWAY AND KUAMOO ROAD</u> | |
| <u>GUARDRAIL AND SHOULDER IMPROVEMENTS</u> | |
| <u>AT VARIOUS LOCATIONS</u> | |
| <u>FEDERAL AID PROJECT NO. STP-0700(38)</u> | |
| Scale: None | Date: Sept, 1996 |
| SHEET No. 1 OF 1 SHEETS | |