

SUMMARY OF QUANTITIES

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	PM5-0700(20)	1981	2	4

KUHIO HIGHWAY (HAENA TO KALUHIWAI)	
	Centerline Striping-L.F.
Begin Project (End of road in Haena) to Wainiha Bridge No. 1	+7,650 14,126
Wainiha Bridge No. 1 to Waioli Bridge	+3,800 16,949
Waioli Bridge to Hanalei Trader	4,214 5,500 (No Pass)
Hanalei Trader to Hanalei Bridge	3,800 5,061
Hanalei Bridge to End Project	+8,800 12,341 *
Total Pavement Striping	53,550 53,391

* Excluded section = Mile Post 27.45 to Mile Post 28.45

SECTIONS TO BE ERADICATED (PASSING AREAS)	
Mile Post 30.43 to 30.62.5	+000 Ft. 1,162
Mile Post 30.68 to 30.74.5	330 Ft. 348
Mile Post 30.81 to 30.87	330 Ft.
Mile Post 30.95 to 30.98	100 Ft.
Mile Post 31.15 to 31.22	750 Ft.
Total Striping to be eradicated	8,600 L.F. 2,780

NOTE:

Sections to be eradicated will be designated by the Engineer.

WAIMEA CANYON DRIVE		
Station	Centerline Striping-L.F.	
Sta. 170+00 to 171+80	2,200 2,203	No Pass
Sta. 171+80 to 177+00	550 477	Pass-No Pass
Sta. 201+00 to 205+00	400 423	No Pass-Pass
Sta. 205+00 to 270+00	6,500 6,510	No Pass
Sta. 270+00 to 274+80	500 454	Pass-No Pass
Sta. 274+80 to 279+60	500 496	No Pass-Pass
Sta. 279+60 to 338+40	5,900 5,911	No Pass
Sta. 338+40 to 342+80	500 410	Pass-No Pass
Sta. 342+80 to 347+20	500 491	No Pass-Pass
Sta. 347+20 to 351+00	400 363	No Pass
Total Pavement Striping	17,950 17,733	

GENERAL NOTES:

- 1- The Contractor shall keep at least one lane open to traffic during working hours and both lanes open to traffic during non-working hours. All lanes shall be open to traffic during peak hours from 6:30 a.m. to 8:00 a.m. and 3:30 p.m. to 5:00 p.m.
- 2- The eradication of existing point striping shall be done by heat, utilizing the excess oxygen concept.
- 3- Removal of raised pavement markers between the Hanalei Trader and Waioli Bridge shall be considered incidental to Item No. 629.1010

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
No.	TRACED BY	
	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
LAND TRANSPORTATION FACILITIES DIVISION
PAVEMENT MARKING AT
VARIOUS LOCATIONS, KAUAI
PHASE II
FED. AID PROJ. NO. PM5-0700(20)
GENERAL NOTES AND
SUMMARY OF QUANTITIES
DEC. 1980
SHEET NO. 1 OF 1 SHEETS