

1 **SECTION 645 - WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **Subsection 645.03 – Construction** by adding this paragraph after
6 line 70:

7
8 “Furnish two Electronic Message Boards or the amount requested by the
9 Engineer for each work site that requires work zone traffic control on a daily basis.”

10
11 **(II)** Amend **645.03 (B) Construction Signs** from line 162 to 169 by changing
12 all references to “Construction Signs” to read “**Work Zone Signs**”.

13
14 **(III)** Amend **Subsection 645.03 Construction** by adding this paragraph after line
15 170 to read as follows:

16
17 **“(1) Covers.** Use sign covers when existing signs confuse the public or
18 are in conflict with TCP signs installed. Sign covers shall be commercially
19 manufactured and accepted by the Engineer before use. Sign covers shall at
20 all times and under all conditions not allow any portion of the sign being
21 covered to be visible. If more than one side of the sign has words or symbols
22 cover all sides of the sign until needed. “Homemade” or “field made” covers
23 shall not be used. Covering of sign identification markings are not required if
24 that is the only markings on that side of the sign. Sign covers shall be
25 maintained.

26
27 Removal of the existing sign in lieu of the use of sign covers may be
28 acceptable to the Engineer provided the previously removed existing sign is
29 immediately reinstalled when directed. Removal of existing post(s) and
30 mounting hardware is required if not used to mount the new TCP sign. New
31 mounting hardware shall be used to mount the TCP signs if the existing
32 hardware is in an unacceptable condition in the opinion of the Engineer. In
33 addition, should the sign or post during storage, in the opinion of the
34 Engineer, become unacceptable or lost or stolen the Contractor shall replace
35 the sign or post with a new sign or post. Use new hardware to reinstall the
36 sign regardless whether it is an existing sign or new.”

37
38 **(IV)** Amend **Subsection 645.03 (F) Lane Closures** Line 253 by changing "Oahu"
39 to “Kauai”.

40
41 **(V)** Amend **Subsection 645.03 (G) Advisory Signs** from Line 314 to Line 324 to
42 read as follows:

43
44 “Advisory signs are not required for this project.”

45
46 **(VI)** Amend **Subsection 645.03 (H) Advertisement** from Line 391 to Line 392 to
47 read as follows:

“Place advertisement for three (3) consecutive days and within one (1) week before traffic pattern changes, in publication as ordered by the Engineer. In lieu of the advertisement(s), the Engineer may substitute the use of two portable changeable message boards and accessories for three (3) days for each required advertisement.”

(VII) Amend **Subsection 645.04 – Measurement** from lines 394 to 403 to read:

“645.04 Measurement. The Engineer will measure Traffic Control as ordered by the Engineer on a force account basis in accordance with the contract documents.”

(VIII) Amend **Subsection 645.05 – Payment** from lines 405 to 424 to read:

“645.05 Payment. The Engineer will pay for the accepted Traffic Control at the contract price on a force account basis in accordance with the contract documents. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will compute the actual amount paid to the Contractor for force account work according to Subsection 109.06 – Force Account Provisions and Compensation.

The Engineer will pay for the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
Traffic Control	Force Account

An estimated amount for force account is allocated in the proposal schedule under ‘Traffic Control’, but actual amount to be paid will be the sum shown on accepted force account records, whether this sum be more or less than the estimated amount allocated in the proposal schedule. The Engineer will pay for traffic control measures requested by the Engineer on a force account basis.”

END OF SECTION 645