

\* Depth varies (8"-12") or as directed by the Engineer.

### TYPICAL PAVEMENT RECONSTRUCTION PAYMENT SECTION

Not to Scale

#### Notes for Reconstruction Areas:

1. Reconstruct weakened pavement areas prior to cold plane.
2. The exposed remaining base course or subbase materials should be properly recompact to dense and unyielding conditions prior to placement of the asphalt concrete base layer.

#### Legend:



-  — Pavement Reconstruction
-  — Cold Plane

FIGURE 1