

1                   **SECTION 414 – RECONSTRUCTION OF WEAKENED PAVEMENT AREAS**

2  
3           Make the following amendment to said Section:

4  
5       **(I)**     Amend **Subsection 414.03 – Construction** by adding the following paragraphs  
6       to read as follows:

7  
8           “The depth of excavation for reconstruction shall be the reconstruction thickness  
9           shown in the contract or as ordered by the Engineer.     Consider the depth of  
10          excavation for reconstruction to be the depth shown on the typical pavement  
11          reconstruction section detail.     Reconstruct the excavated areas according to  
12          Section 301 – Hot Mix Asphalt Base Course.

13          Backfill and thoroughly compact unauthorized excavation below the required  
14          bottom grade with suitable material at no cost to the State.     The finished bottom  
15          grade immediately before placing subsequent material thereon shall be  
16          compacted as specified in Section 110.

17  
18       **(III)**    Amend **Subsection 414.05 – Payment** from lines 31 to 57 to read:

19  
20       **“414.05     Payment.**     The Engineer will pay for the accepted excavation of  
21       weakened pavement areas at the contract unit price per cubic yard.     The price  
22       includes full compensation for removing and disposing of all existing raised  
23       pavement markers and traffic tapes; excavating; saw cutting; compacting the  
24       bottom grade; furnishing, backfilling, and compacting ATB; furnishing and  
25       installing the asphalt concrete pavement; spreading, furnishing, applying the  
26       tack coat; compacting and finishing the asphalt concrete pavement; sampling;  
27       protecting the pavement; installing temporary and/or permanent pavement  
28       markings; disposing excavated materials; and furnishing equipment, tools,  
29       materials, labor, and incidentals necessary to complete the work.

30       The Engineer will make payment under:

31 <b>Pay Item</b>	<b>Pay Unit</b>
32           Reconstruction of Weakened Pavement Areas	Cubic Yard

33  
34  
35                   **END OF SECTION 414**