

SECTION 629 - PAVEMENT MARKINGS

Make the following amendments to said Section:

(I) Amend **Subsection 629.03(B) – Temporary Pavement Markings** by revising the third paragraph from line 62 to 63 to read:

“Maintain and replace temporary pavement markings, flexible delineators, and barricades. ”

(II) Amend **Table 629.03 – 1 – Temporary Pavement Markings** to read as follows:

“TABLE 629.03-1 TEMPORARY PAVEMENT MARKINGS	
TYPE	PAVEMENT MARKINGS
Passing Permitted - Both Sides	Single 4-inch yellow stripe 5 feet in length spaced 20 feet on center with Type D markers spaced 40 feet on center and located on center of 5-foot length of stripe.
Passing Prohibited - Both Sides	Double solid 4-inch yellow stripes with Type D markers placed 20 feet on center on one of 4-inch yellow stripes selected by the Engineer.
Passing Permitted - One Side Only	Single continuous 4-inch yellow stripe with Type D markers placed on stripe 20 feet on center on no-passing side and single 4-inch yellow stripes 5 feet in length spaced 20 feet on center on passing side.
Lane Lines - Lane Changing Permitted	Single 4-inch yellow or white stripe 5 feet in length spaced 20 feet on center with Type C or Type D markers spaced 40 feet on center.
Lane Lines - Lane Changing Prohibited	Double solid 4-inch white stripes with Type C markers placed 20 feet on center on one of the 4-inch white stripes selected by the Engineer.
Crosswalk	Two 12-inch white transverse lines spaced 8 feet on center or as ordered by the Engineer.
Stop Line	Single 12-inch white transverse line.
Note: Paint may be used for temporary markings in areas where final paving is not complete.”	

(III) Amend **Subsection 629.04 – Measurement** by revising the lines 292 to 294 to read as follows:

18 **"629.04 Measurement.** The Engineer will not measure for furnishing and
19 installing pavement striping, pavement markers, detour pavement striping, curb
20 markings, temporary pavement markings, flexible delineator posts with reflector
21 markers, Type I Barricades, temporary signs, crosswalk marking, pavement
22 arrows, pavement words, pavement symbols and removing pavement markings
23 for payment."

24
25 **(IV) Amend Subsection 629.05 – Payment** by revising lines 296 to 330 to
26 read as follows:

27
28 **"629.05 Payment.** The Engineer will not pay for the accepted pavement
29 marking items separately. The Engineer will consider the cost for pavement
30 marking in the contract price of the various contract items in Section 401 – Hot
31 Mix Asphalt Pavement. The cost includes full compensation for maintaining,
32 replacing, and eventually removing the temporary pavement markings, flexible
33 delineators and barricades; and furnishing labor, materials, equipment, tools,
34 and incidentals necessary to complete the work.

35
36 The Engineer will not pay for the accepted removal of existing pavement
37 markings separately. The Engineer will consider the cost for the removal of
38 existing pavement markings as included in the contract price of the various
39 items in Section 401 – Hot Mix Asphalt Pavement. The cost includes full
40 compensation for removing the existing pavement markings, and furnishing
41 labor, materials, equipment, tools, and incidentals necessary to complete the
42 work."

43
44
45 **END OF SECTION 629**