

1 **"SECTION 645 - WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend Subsection 645.03 - Construction** by adding this paragraph after
6 line 70 to read as follows:

7
8 "Furnish two Electronic Message Boards or the amount requested by the
9 Engineer for each work site that requires work zone traffic control on a daily basis."

10
11 **(II) Amend Subsection 645.03 - Construction** by adding this paragraph after
12 line 170 to read as follows:

13
14 **"(1) Covers.** Use sign covers when existing signs confuse the
15 public or are in conflict with TCP signs installed. Sign covers shall be
16 commercially manufactured and accepted by the Engineer before use. Sign
17 covers shall at all times and under all conditions not allow any portion of the
18 sign being covered to be visible. If more than one side of the sign has words
19 or symbols cover all sides of the signs until needed. "Homemade" or "field
20 made" covers shall not be used. Cover both sides of the sign if both sides
21 have symbols or words. Covering of sign identification markings are not
22 required if that is the only markings on that side of the sign. Sign covers shall
23 be maintained."

24
25 **(III) Amend Subsection 645.03(F) - Lane Closures** from lines 253 to 254 to
26 read as follows:

27 "For island of Kauai, no lane closures will be allowed during 24-hour
28 periods as follows"

29
30
31 **(IV) Amend Subsection 645.03(H) - Advertisement** from lines 391 to 392 to
32 read as follows:

33 "Place advertisement for three consecutive days and within three days
34 before traffic pattern changes, in publication as ordered by the Engineer. In lieu of
35 the advertisement(s), the Engineer will substitute the use of two Electronic message
36 boards and accessories for each required advertisement.
37

38
39 **(V) Amend Subsection 645.04 - Measurement** from lines 394 to 403 to read:

40
41 **"645.04 Measurement.**

42
43 **(A)** Traffic control as specified in subsection 645.03 - Construction
44 including sign covers and initial advertisement(s) will be measured per
45 each on a one half (1/2) working day basis in accordance with the
46 contract documents.
47

48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71

(B) The Engineer will not measure Additional Police Officers, Additional Traffic Control Devices, and Advertisement for payment such as hiring the services of additional Police Officers that the Engineer requested; furnishing, installing, maintaining and removing the additional devices; and inserting the legal notices required by the Engineer.

(VI) Amend **Subsection 645.05 - Payment** from lines 405 to 424 to read:

“645.05 Payment. The Engineer will pay for the accepted traffic control at the contract price per each on a one half (1/2) working day basis, as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for the following pay item when included in the proposal schedule:

Pay Item	Pay Unit
Traffic Control	Each”

END OF SECTION 645