

1 Make the following Section a part of the Standard Specifications:  
2

### 3 **SECTION 691 – ARCHAEOLOGICAL MONITORING** 4

5 **691.01 Description.** This work includes monitoring construction activity for  
6 archaeological items at the location shown on the plans and as directed by the  
7 Engineer.  
8

9 Prior to the start of work, an archaeological monitoring plan will be submitted and written  
10 acceptance with comments will be provided by the State Department of Land and  
11 Natural Resources, State Historic Preservation Division. Copies of the accepted  
12 archaeological monitoring plan will be on file at the office of the Engineer upon  
13 acceptance.  
14

15 **691.02 Materials.** None.  
16

17 **691.03 Construction.** In addition to the requirements of Section 107.13 (B) –  
18 Archaeological, Historical, and Burial Site Findings, where construction occurs on  
19 Route 580, Kuamoo Road and on Route 560, Kuhio Highway, the Contractor shall  
20 obtain the services of a qualified Archaeologist or firm to investigate the sites prior to  
21 any ground disturbing activities and to monitor during ground disturbing activities and  
22 excavation activities for historic remains such as artifacts, burials, concentrations of  
23 shell or charcoal. The qualified Archaeologist or firm shall be on the State of Hawaii,  
24 State Historic Preservation's Listing of Permitted Archaeological Firms (See  
25 <https://dlnr.hawaii.gov/shpd/about/branches/archaeology/>) and have the qualification of  
26 HAR 13-281. The Archaeological Monitor's name or firm is not required to be listed on  
27 the Subcontractor Proposal Page of its bid for the subject project.  
28

29 If cultural deposits, cultural features, artifacts, or human skeletal remains are found,  
30 work shall cease in the immediate vicinity of the find and the find shall be protected from  
31 further damage. The Contractor shall immediately follow the protocols set forth in the  
32 Archaeological Monitoring Plan, which will assess the significance of the find and  
33 recommend appropriate mitigation measures, if necessary.  
34

35 **691.04 Measurement.** The Engineer will measure the work required for the  
36 archaeological monitoring, including remedial measures, on a force account basis in  
37 accordance with Subsection 109.06 – Force Account Provisions and Compensation and  
38 as ordered by the Engineer.  
39

40 **691.05 Payment.** The Engineer will pay for the accepted archaeological monitoring,  
41 including remedial measures, on a force account basis in accordance with Subsection  
42 109.06 – Force Account Provisions and Compensation. Payment will be full  
43 compensation for the work prescribed in this section, by the Engineer, and in the  
44 contract documents.  
45  
46

The Engineer will pay for the following pay item when included in the proposal schedule:

**Pay Item**

**Pay Unit**

Archaeological Monitoring

Force Account

The Engineer will not pay for work required that is due to the Contractor's convenience, negligence, carelessness or failure to properly monitor excavation activity.

**END OF SECTION 691**