

1 **SECTION 613 – CENTERLINE AND REFERENCE SURVEY MONUMENTS**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **Subsection 613.03(A) – Initial Installation** from lines 22 to 26 to
6 read:

7
8 **“(A) Initial Installation.** Cut holes, in completed medians and
9 shoulders, to required depth or to solid rock, whichever is less. Fill hole
10 with concrete. Burr or feather plug for anchorage in concrete. Place
11 the 4 #4 x 20-inch bars as shown on the plans when curing the concrete.
12 Install brass plug in required position after concrete has sufficiently set.
13 After curing concrete at least 7 days, restore edge of pavement
14 surrounding monument to original condition.”

15
16 **(II)** Amend **613.04 – Measurement** by revising lines 48 to 56 to read as
17 follows:

18
19 **“613.04 Measurement.**

20
21 **(A)** The Engineer will measure new centerline and reference survey
22 monuments, reconstructing centerline and reference survey monuments,
23 and adjusting centerline and reference survey monuments per each in
24 accordance with the contract documents.”

25
26 **(III)** Amend **613.05 – Payment** by revising lines 62 to 79 to read as follows:

27
28 **“613.05 Payment.**

29
30 **(A)** The Engineer will pay for the accepted new centerline and
31 reference survey monuments, reconstructing centerline and reference
32 survey monuments, and adjusting centerline and reference survey
33 monuments at the contract unit price per each. Payment will be full
34 compensation for work prescribed in this section and the contract
35 documents.

36
37 The Engineer will pay for each of the following pay items when included in
38 the proposal schedule:

	Pay Item	Pay Unit
39		
40		
41		
42	(A) Centerline and Reference Survey Monuments	Each
43		
44	Reconstructing Centerline and Reference Survey Monuments	Each”
45		

46 **END OF SECTION 613**