SECTION 201 – CLEARING AND GRUBBING

Make the following amendments to said Section:

(I) Amend **201.01 – Description** adding the following after line18:

"The following bridges shall include clearing and grubbing of all vegetation within the limits defined below:

1. Kekaha Channel No. 1

Limits of vegetation removal within the following limits:

1. Transversely, beginning at the Ordinary High-Water Mark, or existing water level in the channel, and extending up and 25' past the top of embankment on both sides of the stream.
2. Longitudinally, beginning at the Right of Way line (25' from the highway baseline in both directions) and extending to the highway white line or as far as the vegetation exists in that direction."

(II) Amend **201.04 – Measurement** by revising lines 167 to 168 to read as follows:

"**201.04 Measurement.** The Engineer will measure clearing and grubbing per square yard in accordance with the contract documents."

(III) Amend **201.05 – Payment** by revising lines 170 to 179 to read as follows:

"**201.05 Payment.** The Engineer will pay for the accepted clearing and grubbing per square yard. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for the following pay item when included in the proposal schedule:

Pay Item	**Pay Unit**
Clearing and Grubbing for _____	Square Yard"

END OF SECTION 201