

SECTION 712 - MISCELLANEOUS

Make the following amendments to said Section

(I) Amend **712.40(C) – Reflective Pavement Markers** by revising the first paragraph to read as follows

"(C) Reflective Pavement Markers.. The two types of reflective pavement markers are regular size (nominal 4 inches x 4 inches or 3 5 inches x 4 inches) and low profile size (nominal 2.3 inches x 4 7 inches) "

(II) Amend **712.40(C)(3)(b)** to read as follows

"(b) Regular marker (4 inches by 4 inches or 3 5 inches x 4 inches) shall support a minimum load of 2,000 pounds as applied in the following manner

1. The marker shall be centered, base down, over the open end of a vertically positioned hollow metal cylinder
2. The cylinder shall be 1 -inch high, with an internal diameter of 3-inches and wall thickness of 1/4-inch.
3. The Contractor shall apply a load necessary to break the marker at a speed of 0 2 inch per minute to the top of the marker through a 1-inch diameter solid metal cylinder centered on the top of the marker "

END OF SECTION