

Amend **Section 604 - Manholes, Inlets and Catch Basins** to read as follows

"SECTION 604 - INLETS

604.01 Description. This work includes reconstructing and/or adjusting drain inlets according to the contract

604.02 Materials. Concrete for structures shall be of the class specified. Concrete shall conform to Section 601 - Structural Concrete. If concrete in structures is to come in direct contact with sewage or sewage gases, the Contractor shall modify the proportioning of concrete according to Section 625 - Sewer System

Other materials shall conform to the following

Reinforcing Steel	709.01
-------------------	--------

Frames, Grates, Covers and Ladder Rungs	712 07
---	--------

When the location of manufacturing plants allows, the Engineer may inspect the plants periodically for compliance with specified manufacturing methods. The Engineer may get material samples to verify compliance with the contract. This may be the basis for acceptance of manufacturing lots regarding quality.

The condition of materials will be subject to inspection for acceptance before or during incorporation of materials into the work.

604.03 Construction Requirements.

(A) General. Concrete construction shall conform to Section 503 - Concrete Structures.

Reinforcing steel work shall conform to Section 602 - Reinforcing Steel

A certified welder shall do the shop and field welding according to Section 501 - Steel Structures

(B) Reconstructing and/or Adjusting Drain Inlets. Reconstruct and/or adjust the existing drain inlets to the required elevations according to the contract and as ordered by the Engineer

604.04 Method of Measurement. The Engineer will measure the reconstruction and/or adjustment of drain inlet per each

604.05 Basis of Payment. The Engineer will pay for the accepted reconstruction and/or adjustment of drain inlets at the contract unit price per each complete in place

The price includes full compensation for furnishing and installing frames and grates; removing and disposing of existing frames and grates, adjusting or demolishing; excavating and backfilling, furnishing and placing concrete, furnishing and installing reinforcing steel, furnishing materials, equipment, tools, labor and other incidentals necessary to complete the work

The Engineer will make payment under

Pay Item	Pay Unit
Adjusting Grated Drop Inlet	Each"

END OF SECTION