

1 **SECTION 414 – RECONSTRUCTION OF WEAKENED PAVEMENT AREAS**

2
3 Make the following amendment to said Section:

4
5 **(I) Amend Subsection 414.03 – Construction** by adding the following paragraphs
6 to read as follows:

7
8 “The depth of excavation for reconstruction shall be the reconstruction thickness
9 shown in the contract or as ordered by the Engineer. Consider the depth of
10 excavation for reconstruction to be equal to the thickness of the new pavement
11 section if the contract shows no depth. Reconstruct the excavated areas
12 according to Section 301 – Hot Mix Asphalt Base Course (HMABC).

13 Backfill and thoroughly compact unauthorized excavation below the required
14 bottom grade with suitable material at no cost to the State. The finished bottom
15 grade immediately before placing subsequent material thereon shall have a
16 relative compaction of not less than 95 percent for a depth of 6 inches.”

17 **(II) Amend Subsection 414.04 – Measurement** from lines 28 to 29 to read:

18
19 **“414.04 Measurement.** The Engineer will measure excavation for
20 reconstruction of weakened pavement areas per cubic yard as determined by the
21 Engineer.”

22
23 **(III) Amend Subsection 414.05 – Payment** from lines 31 to 57 to read:

24
25 **“414.05 Payment.** The Engineer will pay for the accepted reconstruction of
26 weakened pavement areas at the contract unit price per cubic yard. The price
27 includes full compensation for removing and disposing of all existing raised
28 pavement markers and traffic tapes; excavating; saw cutting; compacting the
29 bottom grade; backfilling and compacting HMABC; furnishing the asphalt
30 concrete pavement; spreading, furnishing, applying, and protecting the tack
31 coat; compacting and finishing the asphalt concrete pavement; sampling;
32 protecting the pavement; installing temporary pavement markings; disposing
33 excavated materials; and furnishing equipment, tools, materials, labor, and
34 incidentals necessary to complete the work.

35 The Engineer will make payment under:

36 Pay Item	37 Pay Unit
38 Reconstruction of Weakened Pavement Areas	39 Cubic Yard”

39 **END OF SECTION 414**