

1 Make this section a part of the Standard Specifications:

2  
3 **"SECTION 417 – CUT CORES IN EXISTING PAVEMENT**

4  
5 **417.01 Description.** This section is for obtaining 4-inch diameter sample  
6 cores of the existing pavement structure.

7  
8 **417.02 Materials.** None specified.

9  
10 **417.03 Construction.** Obtain 4-inch diameter sample cores of the full depth  
11 of the existing pavement structure at locations and in quantities as directed by  
12 the Engineer. Sampling shall be done with a core drill, and in accordance with  
13 the "Sampling and Testing Guide for Acceptance and Verification" in Hawaii DOT  
14 Highways Division's *Quality Assurance Manual for Material*, Appendix 3. After  
15 coring, the hole shall be filled and compacted with new material to conform to the  
16 surrounding area.

17  
18 **417.04 Measurement.** The Engineer will measure the sample cores per each.

19  
20 **417.05 Payment.** The Engineer will pay for the accepted sample cores at the  
21 contract unit price per each.

22  
23 

Pay Item	Pay Unit
Cut Cores in Existing Pavement	Each"

24  
25  
26  
27 **END OF SECTION 417**