

STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAW.	D-50-01-64	1964	3	5

BEG. OF PROJ. NO. D-50-01-64 & STA. 0+00

SUMMARY OF PERFORATED UNDERDRAIN PIPES			
Station	Length of Pipe Complete In Place Lin. Ft.	Station	Length of Pipe Complete In Place Lin. Ft.
17+00	29 27.33	22+00	31 33.5
17+50	29 27.33	22+50	31 33.5
18+00	29 27.67	23+00	31 33.5
18+50	29 27.67	23+50	31 33.5
20+00	30 33.5	24+00	31 33.5
20+50	31 33.5	24+50	31 33.5
21+00	31 33.5		
21+50	31 33.5		

STA. 22+00 Rt
Existing unproved approach to be abandoned & fencing at E/W restrung across existing opening. This work shall be considered incidental to the various contract items.

+ B.M. Elev 536.25
Spike in Plum Tree

Existing Bridge - 7G

Transverse subdrains to be installed as shown. See summary of lengths this sheet.

26+50
STA. 26+00 Rt
Construct unproved approach as shown - 10' wide. This work shall be considered incidental to the various contract items.

Sta. 17+00 to Sta. 19+18.23 Rt.
Widen and deepen existing ditch. For details see Sheet No. 2.
Estimated Quantity
Ditch Exc. = 45 cy.
77

Sta. 19+18.23 to Sta. 25+50 Rt.
Excavate Drainage Ditch as shown. For details see Sheet No. 2.
Estimated Quantities
Ditch Exc. = 45 cy.
200

