

1 **SECTION 503 - CONCRETE STRUCTURES**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend 503.03(B) Falsework and Centering** by adding the following
6 sentence on line 106 to read as follows:

7
8 "Temporary bracing shall be provided, as necessary to withstand all
9 imposed loads during erection, construction and removal of falsework."

10
11 **(II) Amend 503.03(C)(1) Construction** by adding the following sentence on
12 line 172 to read as follows:

13
14 "Formwork joints shall be filled with approved material that is impervious
15 to moisture, will not stain concrete, and produce a tight joint."

16
17 **(III) Amend 503.03(G) Joints** by adding the following sentence after line
18 595 to read as follows:

19
20 "Prior to backfilling with earth or other materials against the joints, all
21 construction, expansion, contraction, and control joints shall be waterproofed
22 with flashing compound waterproofing as detailed in the contract drawings."

23
24 **(IV) Amend 503.03(G)(3) Contraction Joints** by revising lines 661 to 665 to
25 read as follows:

26
27 **"(3) Contraction Joints.** Place contraction joints in walls and other
28 structures at spacing of not more than 20 feet on centers, at locations indicated
29 in the contract documents, at abrupt changes in height or thickness, and at
30 obtuse corners unless otherwise directed by the Engineer."

31
32
33
34
35 **END OF SECTION 503**
36