

1 **SECTION 603 – CULVERTS AND STORM DRAINS**
2

3 Make the following amendments to said Section:
4

5 **(I) Amend Subsection 603.03(K) Cleaning Culverts** by revising lines 276
6 to 280 to read as follows:
7

8 **“(K) Cleaning Existing Culverts and Drainage Structures.** Clean,
9 remove, and dispose of silt, trash, vegetation growth and any other
10 material found in existing culverts and adjoining drainage structures within
11 project limits when directed by the Engineer. Clean by manual or
12 mechanical means. Discharge of debris or wash water during culvert
13 cleaning into stream, ocean, or State of Hawaii waters will not be allowed.”
14

15 **(II) Amend Subsection 603.04(C)** by revising lines 290 to 292 to read as
16 follows:
17

18 **“(C)** Engineer will measure the directed cleaning of existing culverts and
19 drainage structures on a force account basis in accordance with
20 Subsection 109.06 – Force Account Provisions and Compensation and as
21 ordered by Engineer. The cleaning of culverts and drainage structures
22 constructed or to which work was performed on as required by the
23 Contract Documents shall not be measured but is incidental to those
24 items. The cleaning of existing culverts and drainage structures that
25 require cleaning as the result of the Contractor’s work as well as the
26 material deposited as the result of the Contractor’s means and methods
27 used to control water entering the project shall be part of the BMP plan
28 and therefore shall be incident to that work.”
29
30

31 **END OF SECTION 603**
32