

1 **SECTION 645 – WORK ZONE TRAFFIC CONTROL**
2

3 Make the following amendment to said Section:
4

5 **(I)** Amend **Subsection 645.03** by adding the following new paragraph C on line
6 171 and renumber accordingly:
7

8 **“(C) Sign Covers.** Use sign covers when existing signs confuse the public
9 or are in conflict with TCP signs installed. Sign covers shall be commercially
10 manufactured and accepted by the Engineer before use. Sign covers shall
11 at all times and under all conditions not allow any portion of the sign being
12 covered to be visible. If more than one side of the sign has words or
13 symbols, cover all sides of the signs until needed. “Homemade” or “field
14 made” covers shall not be used. Cover both sides of the sign if both sides
15 have symbols or words. Covering of sign identification markings are not
16 required if that is the only markings on that side of the sign. Sign covers
17 shall be maintained.
18

19 Removal of the existing sign in lieu of the use of sign covers may be
20 acceptable to the Engineer providing the previously existing sign is
21 immediately reinstalled when directed. Removal of existing post(s) and
22 mounting hardware is required if not used by the new TCP sign. New
23 mounting hardware shall be used to mount the TCP signs if the existing
24 hardware is in an unacceptable condition in the opinion of the Engineer. In
25 addition, should the sign or post during storage, in the opinion of the
26 Engineer, become unacceptable or lost or stolen, the Contractor shall
27 replace the sign or post with a new sign or post. Use new hardware to
28 reinstall the sign regardless whether it is an existing sign or new.”
29
30

31 **END OF SECTION 645**
32