

DATE

SURVEY PLOTTED BY

DRAWN BY

TRACED BY

DESIGNED BY

CHECKED BY

ORIGINAL PLAN

NOTE BOOK

DATE

BY

DATE

BY

Station	Raised Pav't. Marker Type				Pavement Striping & Markers						Remarks
	"H" Each	"D" Each	"J" Each	"C" Each	4" Yellow Solid Ft.	4" Double Yellow Solid Ft.	4" White, Solid Ft.	8" White, Solid Ft.	12" White, Solid Ft.	12" White, Solid Ft.	
264 + 70	--	3	8	4	60	--	120	--	--	--	Pass/No pass
265 + 30	--	4	--	4	--	60	120	--	--	--	No Pass
265 + 90	--	--	--	4	--	--	40	--	--	12	40' Gap Kekaha Landfill Rd.
266 + 30	--	4	--	4	--	60	120	--	--	--	No Pass
266 + 90	5	5	24	12	200	--	400	--	--	--	No Pass/Pass
268 + 90	--	84	336	168	--	--	6620	--	--	--	Pass/Pass
302 + 00	--	84	336	168	--	--	--	6740	--	--	Pass/Pass
335 + 70	--	44	176	88	--	--	3540	--	1240	--	Pass/Pass
353 + 40	5	6	24	12	220	--	440	--	125	--	Pass/No Pass
355 + 60	--	3	--	4	--	50	100	--	30	--	No Pass
356 + 10	--	--	--	4	--	--	40	--	30	12	40' Gap Akialoa Rd.
356 + 50	--	4	--	4	--	60	120	--	35	--	No Pass
357 + 10	4	5	20	10	160	--	320	--	90	--	No Pass/Pass
358 + 70	--	10	40	20	--	--	740	--	210	--	Pass/Pass
362 + 40	4	6	20	12	200	--	400	--	115	--	Pass/No Pass
364 + 40	--	4	--	4	--	60	120	--	35	--	No Pass
365 + 00	--	--	--	4	--	--	40	--	25	12	40' Gap Akekeke Rd.
365 + 40	--	4	--	4	--	60	120	--	35	--	No Pass
366 + 00	6	6	24	12	210	--	420	--	120	--	No Pass/Pass
368 + 10	--	6	24	12	--	--	420	--	120	--	Pass/Pass
370 + 20	6	6	24	12	--	--	400	--	115	--	Pass/No Pass
372 + 20	--	3	--	4	--	60	120	--	25	--	No Pass
372 + 80	--	--	--	4	--	--	40	--	20	12	40' Gap Amakihi Rd.
373 + 20	--	4	--	4	--	60	120	--	25	--	No Pass
373 + 80	6	6	24	12	180	--	360	--	100	--	No Pass/Pass
375 + 60	--	6	24	12	--	--	480	--	135	--	Pass/Pass
378 + 00	6	6	24	12	200	--	400	--	115	--	Pass/No Pass
380 + 00	--	4	--	4	--	60	120	--	35	--	No Pass
380 + 60	--	--	--	4	--	--	40	--	25	12	40' Gap Alae Rd.
381 + 00	--	4	--	4	--	60	120	--	35	--	No Pass
383 + 60	6	6	24	12	200	--	400	--	115	--	No Pass/Pass
391 + 40	--	21	80	42	--	--	1560	--	500	--	Pass/Pass
393 + 40	6	6	24	12	200	--	400	--	125	--	Pass/No Pass
394 + 00	--	4	--	4	--	60	120	--	55	--	No Pass
394 + 40	--	--	--	4	--	--	40	--	35	12	40' Gap Kala Rd.
395 + 00	--	4	--	4	--	60	120	--	55	--	No Pass
397 + 50	7	8	28	14	250	--	500	--	140	--	No Pass/Pass
402 + 20	--	12	48	24	--	--	940	--	290	--	Pass/Pass
404 + 80	7	8	28	14	260	--	520	--	145	--	Pass/No Pass
405 + 40	--	4	--	6	--	60	120	--	35	--	No Pass
405 + 80	--	--	--	4	--	--	40	--	20	12	40' Gap Iwa Rd.
409 + 30	--	18	--	20	--	350	700	--	160	--	No Pass
409 + 70	--	--	--	4	--	--	40	--	20	12	40' Gap Moho Rd.
413 + 80	--	22	--	24	--	410	820	--	195	--	No Pass
414 + 20	--	--	--	4	--	--	40	--	15	12	40' Gap Nene Rd.
418 + 20	--	21	--	22	--	400	800	--	140	--	No Pass
418 + 60	--	--	--	4	--	--	40	--	15	12	40' Gap Pueo Rd.

Station	Raised Pav't. Marker Type				Pavement Striping & Markers						Remarks
	"H" Each	"D" Each	"J" Each	"C" Each	4" Yellow Solid Ft.	4" Double Yellow Solid Ft.	4" White, Solid Ft.	8" White, Solid Ft.	12" White, Solid Ft.	12" White, Solid Ft.	
418 + 60	--	41	--	42	--	800	1600	--	340	--	No Pass
426 + 60	--	--	--	4	--	--	40	--	20	12	40' Gap Aukuu Rd.
427 + 00	--	--	--	--	--	--	--	--	--	--	Resurfacing Exception
435 + 50	--	17	--	17	--	330	660	--	--	--	No Pass
438 + 80	--	--	--	4	--	--	40	--	--	12	40' Gap Elepaio Rd.
439 + 20	--	5	--	4	--	70	140	--	--	--	No Pass
439 + 90	--	--	--	4	--	--	40	--	--	12	40' Gap Manu Rd.
440 + 30	--	24	--	24	--	445	890	--	--	--	No Pass
444 + 75	--	--	--	4	--	--	40	--	--	12	40' Gap Akepa Rd.
445 + 15	--	4	--	4	--	60	120	--	--	--	No Pass
445 + 75	--	6	--	24	235	--	470	--	--	--	No Pass/Pass
448 + 10	--	13	52	26	--	--	980	--	--	--	Pass/Pass
453 + 00	7	7	28	14	260	--	520	--	--	--	Pass/No Pass
455 + 60	--	4	--	4	--	60	120	--	--	--	No Pass
456 + 20	--	--	--	4	--	--	40	--	--	12	40' Gap Mamo Rd.
456 + 60	--	4	--	4	--	60	120	--	--	--	No Pass
457 + 20	7	8	28	14	280	--	560	--	--	--	No Pass/Pass
460 + 00	--	22	88	44	--	--	1720	--	--	--	Pass/Pass
468 + 60	6	6	24	12	210	--	420	--	--	--	Pass/No Pass
470 + 70	--	6	--	6	--	90	180	--	--	--	No Pass
471 + 60	--	--	--	4	--	--	40	--	--	12	40' Gap Kekaha Rd.
472 + 00	--	4	--	4	--	70	140	--	--	--	No Pass
472 + 70	--	--	--	4	--	--	40	--	--	12	40' Gap Kekaha Rd.
473 + 10	--	22	--	22	--	430	860	--	--	--	No Pass
477 + 40	8	8	32	--	290	--	580	--	--	--	No Pass/Pass
480 + 30	--	32	128	64	--	--	2526	--	--	--	Pass/Pass
492 + 93											
Totals	96	688	1740	1189	3815	4345	36,526	6,740	5,235	204	

Notes:

- * Tape, Type I or Thermoplastic Extrusion (No passing zones, channelizing lines, solid lines or pavement arrows)
- ** Tape, Type II or Thermoplastic Extrusion (Transverse median markings, transverse shoulder markings, channelizing islands, or edge striping)
- *** Tape, Type III, or Thermoplastic extrusion (Guide lines, stop lines, extension of edge lines, or crosswalk markings)

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-050-1(13)	1994	14	15

LEGEND FOR
AS-BUILT POSTINGS

Squiggly line for
as-built deletion

Double line for
as-built deletion

Text for as-built
posting

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

PAVEMENT MARKING SUMMARY

KAUMUALII HIGHWAY RESURFACING
Kekaha Landfill Road to
Waimea Canyon Drive
Federal-Aid Project No. STP-050-1(13)

Date: September, 1993

SHEET No. 1 OF 1 SHEETS