

## SECTION 629 - PAVEMENT MARKINGS

Make the following amendments to said Section:

(I) Amend **Subsection 629.03(B) – Temporary Pavement Markings** by revising the third paragraph from line 62 to 63 to read:

“Maintain and replace temporary pavement markings, flexible delineators, and barricades. ”

(II) Amend **Table 629.03 – 1 – Temporary Pavement Markings** to read as follows:

“TABLE 629.03-1 TEMPORARY PAVEMENT MARKINGS	
TYPE	PAVEMENT MARKINGS
Passing Permitted - Both Sides	Single 4-inch yellow stripe 5 feet in length spaced 20 feet on center with Type D markers spaced 40 feet on center and located on center of 5-foot length of stripe.
Passing Prohibited - Both Sides	Double solid 4-inch yellow stripes with Type D markers placed 20 feet on center on one of 4-inch yellow stripes selected by the Engineer.
Passing Permitted - One Side Only	Single continuous 4-inch yellow stripe with Type D markers placed on stripe 20 feet on center on no-passing side and single 4-inch yellow stripes 5 feet in length spaced 20 feet on center on passing side.
Lane Lines - Lane Changing Permitted	Single 4-inch yellow or white stripe 5 feet in length spaced 20 feet on center with Type C or Type D markers spaced 40 feet on center.
Lane Lines - Lane Changing Prohibited	Double solid 4-inch white stripes with Type C markers placed 20 feet on center on one of the 4-inch white stripes selected by the Engineer.
Crosswalk	Two 12-inch white transverse lines spaced 8 feet on center or as ordered by the Engineer.
Stop Line	Single 12-inch white transverse line.
<b>Note:</b> Paint may be used for temporary markings in areas where final paving is not complete.”	

(III) Amend **629.05 – Payment** by amending lines 296 to 325 to read as follows:

18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43

**“Section 629.05 Payment.** The Engineer will pay for the accepted pay items listed below at contract price per pay unit as shown in the proposal schedule. Payment will be full compensation for work prescribed in this section and contract documents.

The Engineer will pay for each of the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
12-Inch Pavement Striping (Tape, Type III or Thermoplastic Extrusion)	Lump Sum
Double 4-Inch Pavement Striping (Tape, Type III or Thermoplastic Extrusion)	Lump Sum
4-Inch Pavement Striping (Tape, Type III or Thermoplastic Extrusion)	Lump Sum
Type C Pavement Marker	Lump Sum”

**END OF SECTION 629**