1	SECTION 503 - CONCRETE STRUCTURES
2 3 4	Make the following amendments to said Section:
5 6 7	(I) Amend 503.04 – Measurement by revising lines 1201 to 1205 to read as follows:
8	"503.04 Measurement. The Engineer will measure the concrete by cubic
9	yard according to the dimensions shown in the contract or as ordered by the
10	Engineer.
11	
12	The Engineer will not measure concrete when contracted on a lump sum
13	basis.
14 15	The Engineer will not make deductions for the volume occupied by
16	reinforcing steel, piles, floor drains, weepholes, timber bumpers, pipes less
17	than eight (8) inches, conduits, or expansion joint materials.
18	than orgin (b) monoc, conducto, or expansion joint materials.
19	The Engineer will consider the wingwalls to be a part of the structure."
20	
21	(II) Amend 503.05 - Payment by revising lines 1206 to 1223 to read as
22	follows:
23	#500.05
24	"503.05 Payment. The Engineer will pay for the accepted quantities of
25 26	concrete complete in place at the contract unit price per cubic yard for the pay items listed below and contained in the proposal.
27	items listed below and contained in the proposal.
28	The contract unit price amount paid shall be full compensation for the
29	concrete; for placing, curing and finishing; for furnishing materials including
30	admixtures and cement (including extra cement added to concrete deposited
31	under water); for furnishing and installing drains, scuppers, premolded joint fillers,
32	joint seals, waterproofing at construction joints, waterstops, pipes and conduits;
33	for furnishing and installing metal rockers, anchor bolts, structural shapes for
34	expansion joints and other similar items; for timber bumpers, forms, form lining
35	and falsework or centering, bearing pads, structural steel bearing plates; and for
36	equipment, tools, labor, materials and incidentals necessary to complete the
37	work.
38 39	The Engineer will new for the following new item when included in the
40	The Engineer will pay for the following pay item when included in the proposal schedule:
41	proposal schedule.
42	Pay Item Pay Unit
43	. ay a
44	Concrete in Cubic Yard
45	
46	
47	The Engineer will not pay for excavation and backfill for foundations in
48	accordance with and under Section 205 - Excavation and Backfill for Bridge and

49	Retaining Structures and Section 206 - Excavation and Backfill for Drainage
50	Facilities. The Engineer will consider the cost of for excavation and backfill for
51	foundations in the contract price of Section 503 – Concrete Structures"
52	
53	
54	
55	
56	
57	END OF SECTION 503