

1                                   **SECTION 702 – BITUMINOUS MATERIALS**  
2

3   Make the following amendments to said Section:  
4

5   **(I)**     Amend **Subsection 702.01** by replacing lines 4 to 5 to read:  
6

7   **“702.01   Asphalt Cement.**  
8

9           **(A)   PG 64-16.** Performance graded (PG) asphalt binder (neat or  
10          unmodified) shall conform to AASHTO M 320.  
11

12          **(B)   PG 64E-22.** Performance graded binder (polymer modified) shall  
13          conform to AASHTO M 332 and meet the following additional requirement:  
14

15                 AASHTO T 315 Determining the Rheological Properties of Asphalt  
16          Binder Using a Dynamic Shear Rheometer (DSR). Phase angle on original  
17          binder shall be less than 77 degrees.  
18

19          **(C)   Submittals.** Submit, before usage, a Certificate of Compliance,  
20          accompanied by substantiating test data, showing conformance with  
21          Performance Graded Asphalt Binder Specification. The Engineer will not  
22          accept the PG binder without adequate documentation.”  
23

24   **(II)**     Amend **Subsection 702.06 (Unassigned)** by replacing line 23 to read:  
25

26   **“702.06   Warm Mix Asphalt (WMA) Additive.** Additives for WMA shall be  
27   approved by the Engineer.”  
28  
29  
30  
31  
32  
33

34                                   **END OF SECTION 702**  
35  
36