

1 **SECTION 301 – HOT MIX ASPHALT BASE COURSE**

2
3 Make the following amendments to said Sections:

4
5 **(I) Amend Section 301.03(B) Compaction** by revising the second
6 paragraph from lines 84 to 87 to read as follows:

7
8 “Compact mixture immediately upon completion of spreading operations to
9 density of not less than 92.0 percent of maximum theoretical specific
10 gravity in accordance with AASHTO T 209, modified by deletion of
11 Supplemental Procedure for Mixtures Containing Porous Aggregate.”

12
13 **(II) Amend Section 301.04 Measurement** from lines 98 to 100 to read as
14 follows:

15
16 **“301.04 Measurement.**

17
18 The Engineer will measure HMAB course per ton in accordance with
19 contract documents.”

20
21 **(III) Amend Section 301.05 Payment,** from lines 102 to 111 to read as
22 follows:

23
24 **“301.05 Payment.** The Engineer will pay for the accepted pay item listed
25 below at the contract price per pay unit, as shown in the proposal schedule.
26 Payment will be full compensation for the work prescribed in this section and the
27 contract documents.

28
29 The Engineer will pay for the following pay item when included in the
30 proposal schedule:

31

Pay Item	Pay Unit
Hot Mix Asphalt Base Course	Ton
(1) 80% of the contract unit price upon completion of submitting a job-mix formula acceptable to the Engineer; preparing the surface, spreading, and finishing the mixture; and compacting the mixture by rolling;	
(2) 20% of the contract unit price upon completion of cutting samples from the compacted pavement for testing; placing and compacting the sampled area with new material conforming to the surrounding area; protecting the pavement; and final analysis.”	

45

46 **END OF SECTION 301**