

1 **SECTION 301 – HOT MIX ASPHALT BASE COURSE**

2
3 Make the following amendments to said Sections:

4
5 **(I) Amend Section 301.03(B) Compaction** by revising the second
6 paragraph from lines 84 to 87 to read as follows:

7
8 “Compact mixture immediately upon completion of spreading
9 operations to density of not less than 92.0 percent of maximum theoretical
10 specific gravity in accordance with AASHTO T 209, modified by deletion of
11 Supplemental Procedure for Mixtures Containing Porous Aggregate.”
12

13
14 **(II) Amend Section 301.04 Measurement** from lines 98 to 100 to read as
15 follows:

16
17 **“301.04 Measurement.** The Engineer will measure HMAB course per ton
18 in accordance with contract documents.”
19

20
21 **(III) Amend Section 301.05 Payment,** from lines 102 to 111 to read as
22 follows:

23
24 **“301.05 Payment.** The Engineer will pay for the accepted pay item listed
25 below at the contract price per pay unit, as shown in the proposal schedule.
26 Payment will be full compensation for the work prescribed in this section and the
27 contract documents.
28

29 The Engineer will pay for the following pay item when included in the
30 proposal schedule:

31

32 Pay Item	33 Pay Unit
34 Hot Mix Asphalt Base Course	35 Ton

36 The Engineer will pay for :

37
38 **(A)** 80% of the contract unit price upon completion of submitting
39 a job-mix formula acceptable to the Engineer; preparing the
40 surface, spreading, and finishing the mixture; and compacting the
41 mixture by rolling;
42

43 **(B)** 20% of the contract unit price upon completion of cutting
44 samples from the compacted pavement for testing; placing and
45 compacting the sampled area with new material conforming to the
46 surrounding area; protecting the pavement; and final analysis.

The Engineer may, in lieu of requiring removal and replacement, use the sliding scale factor to accept HMAB compacted below 92.0 percent. The Engineer will make payment for the material in that production day at a reduced price arrived at by multiplying the contract unit price by the pay factor shown in Table 301.05-1.

Table 301.05-1 – Sliding Scale Pay Factor	
Percent Compaction	Percent Payment
92.0 or greater	100
90.0 – 91.9	80
<90.0	Removal

END OF SECTION 301