

SECTION 703 – AGGREGATES

Make the following amendments to said Section:

(I) Amend **TABLE 703.01-3 FINE AGGREGATE GRADING REQUIREMENTS, HAWAII AND KAUAI** to read as follows:

“

TABLE 703.01-3 - FINE AGGREGATE GRADING REQUIREMENTS, HAWAII AND KAUAI		
Sieve Sizes	Percent Passing by Weight	
	Calcareous Sand	Crusher Screenings
3/8 Inch	100	100
No. 4	95 – 100	95 - 100
No. 8	-	50 - 85
No. 16	-	32 - 60
No. 30	-	-
No. 50	-	15 - 30
No. 100	0 – 5	5 - 20

END OF SECTION 703