

1
2
3
4
5
6
7
8
9
0
1
2
3
4
5
6
7
8
9
0
1
2
3
4
5
6
7
8
9
0
1
2
3
4
5
6
7
8
9
0
1
2
3
4
5
6

(l) Amend Subsection 750.01(A)(1) Retroreflectorization by replacing lines 8 through 31 to read:

(a) Background for illuminated guide signs and exit number panels ("E" designation) with ASTM D 4956 Type XI retroreflective sheeting.

(c) Messages, arrows, and borders of guide signs and exit number panels ("D" and "E" designations) with ASTM D 4956 Type XI retroreflective sheeting.

(e) Pedestrian, school, bicycle crossing series, completely with Type IX fluorescent yellow green retroreflective sheeting.”

“(E) Retroreflective Sheeting Materials. Retroreflective sheeting includes white or colored sheeting having smooth outer surface.

The coefficient of retroreflection shall meet the minimum requirements of ASTM D 4956 for the type of reflective sheeting specified.

The color shall conform to the latest appropriate standard color tolerance chart issued by the U.S. Department of Transportation, Federal Highway Administration and to the daytime and nighttime color requirements of ASTM D 4956.

47 Test methods and procedures shall be in accordance with ASTM.”
48 (III) Amend **Subsection 750.02 Sign Posts** by replacing lines 1168 through
49 1172 to read:

50
51 **“750.02(C) Square Tube Posts.** Square and other tube posts shall conform to
52 ASTM A 653 for cold-rolled, carbon steel sheet, commercial quality; or ASTM A
53 787 for electric-resistance-welded, metallic-coated carbon steel mechanical
54 tubing.”

55
56
57
58
59
60
61
62
63
64
65

END OF SECTION 750