

1 **SECTION 755 – PAVEMENT MARKING MATERIALS**

2
3 Make the following amendments to said Sections:

4
5 **(I) Amend Subsection 755.02 (C) Retroreflective Pavement Markers** by
6 revising lines 223 to 236 to read:

7
8 “Exterior surface of shell shall be smooth and contain one or two
9 retroreflective faces of specified color.”

10
11 **(II) Amend Subsection 755.05 (C)(1) Glass Beads** by adding the following
12 after line 869:

13
14 **“(f) The glass spheres shall not contain more than 200 ppm (total)**
15 **arsenic, 200 ppm (total) antimony nor more than 200 ppm (total)**
16 **lead, when tested according to EPA Methods 3052 and 6010C.**
17 **Other suitable x-ray fluorescence spectrometry analysis methods**
18 **may be used to screen samples of glass spheres for arsenic and**
19 **lead content.”**

20
21
22
23
24
25
26
27 **END OF SECTION 755**