

1 **SECTION 717 – CULLET AND CULLET-MADE MATERIALS**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend Subsection 717.01 – Cullet and Cullet-Aggregate Mixtures as**
6 **Construction Materials** by revising the third paragraph from lines 16 to 20 to

7 read:
8
9 “Debris shall not exceed values specified in Tables 717.02-1 – Cullet in
10 Roadway Applications, 717.03-1 – Cullet in Utility Applications, and 717.04-1 –
11 Cullet in Drainage Applications. Debris is defined as deleterious material that
12 includes plastics, papers, and non-ceramic constituents of cullet. Hazardous
13 material will not be allowed in cullet such as but not limited to, TV or other
14 cathode ray tubes, fluorescent light bulbs, and any toxic or hazardous materials.
15 Test cullet stockpile for toxic or hazardous materials every 90 days and submit
16 the results to the Engineer.”

17
18 **(II) Amend Subsection 717.01 – Cullet and Cullet-Aggregate Mixtures as**
19 **Construction Materials** by adding the following paragraph after line 21:

20
21 “Cullet shall not be used in concrete.”

22
23 **(III) Amend Table 717.03-1 – Cullet in Utility Applications** from lines 37 to
24 line 39 to read:

25

TABLE 717.03-1 - CULLET IN UTILITY APPLICATIONS		
Utility Trench Bedding and Backfill Applications	Maximum Cullet Content (Percent By Weight)	Maximum Debris Level (Percent By Weight Of Cullet)
Sewer Pipes	25	0.3
Electrical Conduits	25	0.3
Fiber Optic Lines	25	0.3

(IV) Amend Table 717.04-1 – Cullet in Drainage Applications from lines 47 to line 49 to read:

TABLE 717.04-1 - CULLET IN DRAINAGE APPLICATIONS		
Drainage Fill Applications	Maximum Cullet Content (Percent By Weight)	Maximum Debris Level (Percent By Weight Of Cullet)
Retaining Walls	25	0.2
Foundation Drains	25	0.2
Drainage Blankets	25	0.2
French Drains	25	0.2

END OF SECTION 717