

1                                   **SECTION 503 - CONCRETE STRUCTURES**

2  
3    Make the following amendments to said Section:

4  
5    **(I)     Amend 503.04 – Measurement** by revising lines 1201 to 1205 to read as  
6    follows:

7  
8    **“503.04       Measurement.**   The Engineer will measure the various concrete  
9    items for payment at the units specified in the proposal schedule. The concrete  
10   for the superstructure shall be cast onto the new bridge girders prior to erecting  
11   into position. The concrete for the extension of the stairs shall be cast-in-place  
12   with an expansion joint cast between the cast-in-place concrete and the precast  
13   concrete deck.”

14  
15   **(II)    Amend 503.05 – Payment** by revising lines 1206 to 1223 to read as  
16   follows:

17  
18   **“503.05       Payment.**   The Engineer will pay for the accepted quantities of  
19   concrete complete in place at the pay unit listed below and contained in the  
20   proposal schedule.

21  
22       The contract amounts paid shall be full compensation for the concrete; for  
23   placing, curing and finishing; for furnishing materials including admixtures and  
24   cement; for furnishing and installing premolded joint fillers, joint seals,  
25   waterproofing at construction joints, and pipes; for furnishing and installing  
26   anchor bolts, and other similar items; form lining and falsework or centering,  
27   bearing pads, structural steel bearing plates; and for equipment, tools, labor,  
28   materials and incidentals necessary to complete the work.

29  
30       The Engineer will pay for the following pay items when included in the  
31   proposal schedule:

32

33                   Pay Item	34                   Pay Unit
35   Concrete in Bridge Superstructure	36                   Cubic Yard
37   Concrete in Stair Extensions	38                   Cubic Yard
39   Concrete Spall Repair Type I	40                   Square Foot
41   Concrete Spall Repair Type II	42                   Linear Foot”

43  
44  
45  
46

47                                   **END OF SECTION 503**