

SECTION 629 - PAVEMENT MARKINGS

Make the following amendments to said Section:

(I) Amend **Subsection 629.03(B) – Temporary Pavement Markings** by revising the third paragraph from line 62 to 63 to read:

“Maintain and replace temporary pavement markings, flexible delineators, and barricades. ”

(II) Amend **Table 629.03 – 1 – Temporary Pavement Markings** to read as follows:

“TABLE 629.03-1 TEMPORARY PAVEMENT MARKINGS	
TYPE	PAVEMENT MARKINGS
Passing Permitted - Both Sides	Single 4-inch yellow stripe 5 feet in length spaced 20 feet on center with Type D markers spaced 40 feet on center and located on center of 5-foot length of stripe.
Passing Prohibited - Both Sides	Double solid 4-inch yellow stripes with Type D markers placed 20 feet on center on one of 4-inch yellow stripes selected by the Engineer.
Passing Permitted - One Side Only	Single continuous 4-inch yellow stripe with Type D markers placed on stripe 20 feet on center on no-passing side and single 4-inch yellow stripes 5 feet in length spaced 20 feet on center on passing side.
Lane Lines - Lane Changing Permitted	Single 4-inch yellow or white stripe 5 feet in length spaced 20 feet on center with Type C or Type D markers spaced 40 feet on center.
Lane Lines - Lane Changing Prohibited	Double solid 4-inch white stripes with Type C markers placed 20 feet on center on one of the 4-inch white stripes selected by the Engineer.
Crosswalk	Two 12-inch white transverse lines spaced 8 feet on center or as ordered by the Engineer.
Stop Line	Single 12-inch white transverse line.
Note: Paint may be used for temporary markings in areas where final paving is not complete.”	

(III) Amend **629.04 – Measurement** by revising lines 292 to 294 to read as follows:

19 **"629.04 Measurement.**

20
21 The Engineer will measure thermoplastic and preformed pavement
22 marking tape per linear foot in accordance with the contract
23 documents. The longitudinal pavement markings will be measured per
24 linear foot as a single stripe for the width specified in the contract and
25 in the proposal. The Engineer will include the longitudinal gaps for skip
26 striping, up to thirty (30) feet long, in the measurement.

27
28 The Engineer will measure the transverse markings by the linear
29 foot according to the contract.

30
31 The Engineer will not measure temporary pavement markings
32 including flexible delineator posts with reflector markers or Type I
33 Barricades and temporary signs installed for the longitudinal guidance
34 of public traffic over reconstructed areas, cold planed surfaces, newly
35 paved surfaces or other unmarked or scarified areas for payment.

36
37 The Engineer will measure the temporary pavement markings and
38 temporary signs installed as ordered by the Engineer for special
39 temporary traffic patterns on a force account basis, if the contract
40 specifies payment in the proposal.

41
42 The Contractor shall consider the work required for the removal of
43 pavement markings incidental to the various contract items, except as
44 provided in the proposal or elsewhere in the contract. If the contract
45 stipulates that the Engineer will make payment for the removal of
46 pavement markings, the Engineer will measure the removal of
47 pavement markings.

48
49 The Engineer will measure the pavement markers per each for the
50 types shown in the proposal.

51
52 The Engineer will measure the painted stripes that are twelve (12)
53 inches wide or less as a single stripe. The Engineer will measure the
54 painted stripes over twelve (12) inches wide as two (2) stripes. The
55 Engineer will measure the double stripes that are twelve (12) inches or
56 less in total width including the transverse space between the stripes
57 as a single stripe.

58
59 The Engineer will measure the longitudinal pavement markings by
60 the linear foot according to the contract. Longitudinal gaps for skip
61 striping that are 30 feet or less will be included in the measurement.

62
63 The Engineer will measure the transverse markings by the linear
64 foot according to the contract.

66 The Engineer will measure pavement arrow and word per each in
67 accordance with the contract documents.

68
69 The Engineer will measure yield line per lane in accordance with
70 the contract documents.”

71
72 (IV) Amend **629.05 – Payment** by revising lines 296 to 330 to read as follows:

73
74 **“629.05 Payment.**

75
76 The Engineer will pay for thermoplastic and preformed pavement
77 marking tape at the contract price per linear foot according to the
78 contract, complete in place, including primers.

79
80 The Engineer will pay for double four (4) inch striping with a four (4)
81 inch space between stripes at the contract price per linear foot
82 according to the contract.

83
84 The Engineer will pay for pavement arrows (single and multiple
85 heads), symbols, and words at the contract price per each according to
86 the contract.

87
88 The contract unit price paid shall be full compensation for furnishing
89 labors, materials, tools, equipment and incidentals and for doing the
90 work involved in furnishing and installing pavement markings complete
91 in place according to the contract.

92
93 The Engineer will not pay for the temporary pavement markings
94 including flexible delineator posts with reflector markers or Type I
95 Barricades and temporary signs installed for the longitudinal guidance
96 of public traffic over reconstructed areas, cold planed surfaces, newly
97 paved surfaces or other unmarked or scarified areas for payment if not
98 shown in the proposal separately. The Engineer will consider them
99 incidental to the various contract items.

100
101 If the contract specifies payment for temporary pavement markings
102 installed as ordered by the Engineer for special temporary traffic
103 patterns, the Engineer will pay from an allowance for “Temporary
104 Construction Zone Markings”.

105
106 If the contact specifies payment for removal of pavement markings
107 under unit price pay items, the Engineer will pay for the accepted
108 quantities at the contract unit prices bid. The prices shall be full
109 compensation for removing such items according to the contract.

The Engineer will pay for the various types of pavement markers at the contract price per each according to the contract, complete in place, including adhesives.

The Engineer will pay for the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
_____ - Inch Pavement Striping (Tape, Type ____, or Thermoplastic Extrusion)	Linear Foot
Pavement Arrow (Tape, Type ____, or Thermoplastic Extrusion)	Each
Pavement Word (Tape, Type ____, or Thermoplastic Extrusion)	Each
Type _____ Pavement Marker	Each
Yield Line (Tape, Type _____ or Thermoplastic Extrusion)	Lane"

END OF SECTION 629