

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-0700(35)	1996	3	39

GENERAL NOTES

1.

The scope of work for this project consists of removing existing metal guardrail and posts, installing new metal guardrail and posts, new reflector markers, road excavation, aggregate base, A.C. pavement, and constructing culvert extension.
2.

The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3.

The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 - Public Convenience and Safety, Subsection 107.21 - Contractor's Responsibility for Utility Property and Services, Section 645 - Traffic Control.
4.

At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5.

The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
6.

The Contractor shall notify the State in writing, two (2) weeks prior to starting paving operations.
7.

The Contractor shall remove and dispose of all existing raised pavement markers prior to the overlaying of Asphalt Concrete. This work shall be considered incidental to Asphalt Concrete Pavement, Mix No. IV and will not be paid for separately.
8.

Smooth riding connections shall be constructed at all connections to existing pavement, including connecting approaches, side streets and driveways as shown on the plans and/or as directed by the Engineer.
9.

Dressing of shoulder shall consist of clearing, grubbing, grading, reshaping and compacting the unpaved shoulders with suitable excavated material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.
10.

Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to the various contract items.
11.

The Contractor shall verify the locations of all existing culverts and utilities in the field. Any existing culverts and utilities damaged during construction shall be repaired or replaced by the Contractor at his own expense.
12.

Demolishing, removing, and replacing of existing inlets and headwalls shall not be paid for separately, but shall be considered incidental to the various Contract Items.

13.

Earth swale shall be graded to drain. This work shall be considered incidental to the various contract items.
14.

Contractor shall provide for access to and from all existing side streets at all times.
15.

All saw cutting work shall be considered incidental to Asphalt Concrete Pavement, Mix No. IV.

LEGEND

- o<sub>jp</sub>

Existing Joint Pole
- o<sub>pp</sub>

Existing Power Pole
- e—

Existing Electrical Line
- s—

Existing HTCO Line
- w—12"

Existing Water Line
- o<sub>wv</sub>

Existing Water Valve
- ✧<sub>fh</sub>

Existing Fire Hydrant

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	TRACED BY	
	NOTED BY	
NOTE BOOK	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

GENERAL NOTES

KAUMUALII HIGHWAY AND HALEWILI ROAD

GUARDRAIL AND SHOULDER

IMPROVEMENTS AT VARIOUS LOCATIONS

Federal Aid Project No. STP-0700(35)

Scale: As Shown      Date: June, 1995

SHEET No. 1 OF 1 SHEETS