

Amend **Section 621 - Traffic Control Signs** to read as follows:

"SECTION 621C - MARKERS

621C.01 Description. This section describes furnishing and installing reflector, object, and milepost markers and post.

621C.02 Materials.

Reflector Marker	712.21
Flexible Delineator Post	712.51
Fasteners for Signs	713.12

621C.03 Construction Requirements.

(A) Marker Posts. Set marker posts plumb. Provide marker posts of the following type:

(1) Metal Posts. Zinc-coat metal posts. Provide 1.12 pounds per foot flanged channel posts or 1.5 inch, 12 or 14 gauge square tube posts.

(2) Flexible Posts. Provide flexible post.

(B) Markers.

(1) Reflector Marker. Provide reflector marker of the following type:

(a) RM-1, RM-2, and RM-3 reflector markers conforming to the following:

(1) Type III or IV retroreflective sheeting markers,

(2) Glass sphere reflector markers with 4 - inch by 5 - inch reflector units, or

(3) Plastic prismatic reflector markers with 3 inch diameter reflector units.

(b) RM-4 reflector marker conforming to Type III or IV retroreflective sheeting marker.

(c) RM-9 reflector marker conforming to the following:

48 (1) Nine 3-inch round amber plastic prismatic
49 reflectors fastened with blind rivets to yellow Type III
50 or IV retroreflective sheeting marker, or

51
52 (b) Yellow Type III or IV retroreflective sheeting
53 marker.

54
55 (2) **Type II Object Marker.** Conform reflective sheeting
56 material for Type II object markers to Subsection 712.20(C)(4) -
57 Type III or IV Retroreflective Sheeting.

58
59 **621C.04 Method of Measurement.** Reflector marker, mile post marker, and
60 object marker will be paid on a lump sum basis. Measurement for payment will
61 not apply.

62
63 **621C.05 Basis of Payment.** The Engineer will pay for the accepted pay items
64 listed below on a contract lump sum basis as shown in the proposal schedule.
65 Payment will be full compensation for the work prescribed in this section and the
66 contract documents.

67
68 The Engineer will pay for each of the following pay item when included in
69 the proposal schedule:

70	71 Pay Item	72 Pay Unit
73	Reflector Marker _____	Lump Sum
74	Mile Post Marker with Post (Bi-Directional)	Lump Sum
75	Mile Post Marker _____	Lump Sum
76	Type II Object Marker	Lump Sum"

77
78
79
80
81
82
83
84 **END OF SECTION 621C**