

SECTION 602 - REINFORCING STEEL

Make the following amendments to said Section:

(I) Amend **602.07 Method of Measurement** and **602.08 Basis of Payment** to read as follows:

"602.07 Method of Measurement. The Engineer will not measure reinforcing steel for payment.

The Engineer will base the weights calculated according to Table 602-III.

TABLE 602-III - BAR DESIGNATION, WEIGHT, AND AREA		
Bar No.	Weight Per Linear Foot (Pounds)	Area (Square Inches)
3	0.376	0.11
4	0.668	0.20
5	1.043	0.31
6	1.502	0.44
7	2.044	0.60
8	2.670	0.79
9	3.400	1.00
10	4.303	1.27
11	5.313	1.56
14S	7.650	2.25
18S	13.600	4.00

The Engineer will not make allowance for clips, wire or other material used for fastening reinforcement in place.

The Engineer will not measure mesh reinforcement.

602.08 Basis of Payment. The Engineer will not pay for reinforcing steel separately. The Engineer will consider the cost for reinforcing steel as included in the contract price of the various contract items.

The cost shall be for furnishing and testing sample splices and completed splices cut from rebars placed in the work, including replacing or resplicing rebars to the length shown in the contract; furnishing access facilities to permit the Engineer to do the tests, and for losses or delays to the Contractor resulting from the sampling and testing specified herein; and furnishing labor, equipment, materials, tools and incidentals necessary to complete the work.

The Engineer will not pay for mesh reinforcement separately. The Engineer will consider the cost for mesh reinforcement as included in the bid price of the various contract items."

END OF SECTION