

1 Amend **Section 310 - Brooming Off** to read as follows:
2

3 **"SECTION 310 - BROOMING OFF**
4

5 **310.01 Description.** This work includes cleaning an existing surface or a
6 pavement according to the contract.
7

8 **310.02 Materials.** None specified.
9

10 **310.03 Construction Requirements.** Remove earth, dust or other foreign
11 material and existing raised pavement markers from the entire area in question.
12 Remove raveled materials from pockets in the surface. Remove e grass or
13 other growth from edges of the area. Crop the adjacent growth closely to
14 prevent interference with subsequent operations. Dispose of debris resulting
15 from the cleaning operations.
16

17 Clean the edges of the existing surface so that their original thickness and
18 width may be reconstructed.
19

20 Remove loose material and excess dust by mechanically operated broom
21 or air pressure, supplemented by hand brooming where required. Apply air
22 pressure through pipe nozzles operating from a compressor producing 100 psi
23 pressure. Do this work while the surface is thoroughly dry.
24

25 **310.04 Method of Measurement.** The Engineer will not measure brooming
26 off for payment.
27

28 **310.05 Basis of Payment.** The Engineer will not pay for brooming off
29 separately and will consider the cost for brooming off as included in the contract
30 price of the various contract items. The cost is for the work prescribed in this
31 section and the contract documents."
32
33
34

35 **END OF SECTION**
36
37
38
39