

1 **SECTION 702 - BITUMINOUS MATERIAL**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend 702.01 Asphalt Cement** to read as follows:

6
7 **"702.01 Asphalt Cement.** Performance graded asphalt binder shall conform to
8 AASHTO M 320. "

9
10 (Table deleted.)

11
12 **(II) Amend 702.04 Emulsified Asphalts** to read as follows:

13
14 **"702.04 Emulsified Asphalt.** Anionic emulsified asphalt shall conform to
15 AASHTO M 140, except that the penetration on residue for Type SS-1 and Type
16 RS-1 shall be 50-120 in lieu of the 100-200 specified.

17
18 Cationic emulsified asphalt shall conform to AASHTO M 208, except that the
19 penetration on residue for Type CSS-1 and Type CRS-2 shall be 50-150 in lieu of
20 the 100-250 specified."

21
22
23
24
25
26 **END OF SECTION**