

SECTION 602 – Reinforcing Steel

Make the following amendments to said Section:

(I) Amend **602.04 – Measurement** by revising lines 803 to 808 to read as follows:

“602.04 Measurement. Reinforcing steel will be measured by the pound, based on the theoretical number of pounds complete in place as shown on the plans or placed as ordered as specified in the proposal.

The Engineer will not measure reinforcing steel when contracted on a lump sum basis.

The Engineer will base the weights calculated upon Table 602.04-1 – Bar Designation, Weight and Area.

TABLE 602.04-1 – BAR DESIGNATION, WEIGHT AND AREA		
Bar No.	Weight Per Linear Foot (Pounds)	Area (Square Inches)
3	0.376	0.11
4	0.668	0.20
5	1.043	0.31
6	1.502	0.44
7	2.044	0.60
8	2.670	0.79
9	3.400	1.00
10	4.303	1.27
11	5.313	1.56
14	7.650	2.25
18	13.600	4.00

The Engineer will not make allowance for clips, wire or other material used for fastening reinforcement or bar lengths used for laps. The cost is for the work prescribed in this section and the contract documents.

The Engineer will not measure mesh reinforcement.”

(II) Amend **602.05 – Payment** by revising lines 810 to 830 to read as follows:

“602.05 Payment. The Engineer will pay for the accepted reinforcing steel at the contract unit price per pound or at the contract lump sum price for the contract items specified in the proposal.

The Engineer will pay for the following pay item when included in the proposal schedule:

Pay Item	Pay Unit
Reinforcing Steel for Catch Basin	Lump Sum
Reinforcing Steel for Concrete Collar	Lump Sum”

END OF SECTION 602