

SECTION 631 – TRAFFIC CONTROL, REGULATORY, WARNING, AND MISCELLANEOUS SIGNS

Make the following amendment to said Section:

(I) Amend Section 631.02 Materials, line 14 to read:

“Fasteners for Signs and Route Markers	750.03
--	--------

RRFB Assembly	750.10"
---------------	---------

(II) Amend Section 631.03(C) Labeling of Signs, from lines 42 to 51 to read:

“(C) Labeling of Signs. Label back of each sign with sign stickers as directed by the State. Sign stickers will be provided by the State.”

(III) Amend Section 631.04 – Measurement by replacing lines 67 to 69 to read:

“631.04 Measurement. The Engineer will measure regulatory signs, warning signs, emergency management signs, miscellaneous signs, and RRFB assemblies as complete units of the type and design specified in the proposal.

The Engineer will not measure removal and disposal and storing of existing and temporary signs that the Contractor will not incorporate in the completed highway for payment.”

(IV) Amend Section 631.05 – Payment by replacing lines 71 to 99 to read as follows:

“631.05 Payment. The Engineer will pay for regulatory signs, warning signs, emergency management signs, miscellaneous signs, and RRFB assemblies at the contract price per each for the type and design specified complete in place. Payment will be full compensation for excavating and backfilling, furnishing and installing materials, furnishing equipment, tools, labors and incidentals necessary to complete the work.

The Engineer will not pay for removing and disposing or storing of existing and temporary signs that the Contractor will not incorporate in the completed highway separately. The Engineer will consider them incidental to the various contract items.

The Engineer will pay for the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
Regulatory Sign (10 Square Feet or Less) and Post	Each

48		
49	Regulatory Sign (10 Square Feet or Less)	Each
50		
51	Warning Sign (With Supplemental Plaque) and Post	Each
52		
53	Emergency Management Sign With Supplemental Plaque	Each
54		
55	Relocation of Existing Sign and Post	Each
56		
57	RRFB Assembly	Each"
58		
59		
60		

END OF SECTION 631