

## SECTION 712 - MISCELLANEOUS

Make the following amendments to said Section:

**(I) Amend Subsection 712.06 Precast Concrete Unit** by adding the following after line 94:

**"(C) Polymer Concrete Pull Box.** Pull box for Spectrum shall be precast polymer concrete with woven fiberglass reinforcement and with rated minimum test load of 22,500 pounds. Polymer concrete cover shall likewise have a rated minimum test load of 22,500 pounds and shall be a single piece with two penta-head stainless steel locking bolts.

**END OF SUBSECTION 712**