If design requirements are modified after the Engineer accepts jobmix formula, submit new job-mix formula before using slurry seal produced from modified mix design.

(D) Material Storage & Handling. A barrier shall be placed under the aggregate stockpile to prevent underlying material from being incorporated into the slurry seal aggregate. Prior to loading aggregates into mixing machine bins, aggregates shall be screened to remove oversized material.

404.03 Construction.

- Test Section. Before production and after calibration as specified (A) in Subsection 404.03(D)(6) - Equipment Calibration, apply slurry seal onto test section using same mixture, equipment, and method proposed for use in the work. Test section shall be at least 10 feet by 50 feet and applied under typical project environmental conditions. A separate test section is required for each piece of equipment that will be used on the project. The test sections shall also include a demonstration of the equipment change-out procedure for material resupply to verify the consistency of the slurry material upon restart and the ability to construct an acceptable construction joint. The Engineer will determine location of test section. Prior to continuation of slurry seal production, mixture samples may be taken and the test strip will be evaluated to verify mix consistency, proportioning, application rate, and set time.
- (B) Paving Plan. Submit a slurry seal paving plan for review and acceptance prior to the start of slurry seal activity. The paving plan shall include the sequence of work for the slurry application areas, equipment application runs, and designated handwork application areas.
- **(C) Weather Limitation.** Application of slurry seal will not be allowed under the following conditions:
 - (1) On wet surfaces as determined by the Engineer.
 - (2) When air temperature is below 60 degrees F and falling. Slurry seal may be applied when air temperature is above 50 degrees F and rising. Air temperature will be measured in shade and away from artificial heat.
 - (3) When weather conditions prevent proper method of construction.

94	(D)	Equipment.
95		
96		(1) General. Keep equipment, tools, and machinery clean and
97		maintained in satisfactory condition.
98		·
99		(2) Mixing Equipment. Use self-propelled machine specifically
100		designed and manufactured to lay slurry seal. Mixing machine shall
101		be either truck-mounted or continuous-run design. A continuous-run
102		machine is defined as one that is equipped to self-load while
103		continuing to lay slurry seal. Either type machine shall be able to
104		accurately deliver and proportion aggregate, emulsified asphalt,
105		water, and if specified by job-mix formula, filler to maintain
106		adequate supply to the proportioning controls.
107		
108		If continuous-run machine is used, equip to allow operator to
109		have full control of forward and reverse speeds during slurry seal
110		application; and to include opposite-side driver stations and forward
111		and reverse speed controls.
112		
113		(3) Proportioning Devices. Provide and label individual volume
114		or weight controls for proportioning each material to be added to
115		mix.
116		
117		(4) Spreading Equipment. Spread mixture uniformly by means
118		of conventional surfacing spreader box attached to mixer and
119		equipped to agitate and spread material evenly throughout box.
120		Provide front seal that prevents loss of mixture at road contact point
121		and adjustable rear seal the functions as final strike-off. Design and
122		operate spreader box and rear strike-off such that uniform
123		consistency is achieved to produce free flow of material to rear
124		strike-off. Equip spreader box with means to side shift box to
125		compensate for variations in pavement geometry. Burlap drag or
126		other accepted screed may be attached to rear of spreader box to
127		provide uniform, highly textured mat.
128		(-)
129		(5) Auxiliary Equipment. Provide other tools or equipment,
130		such as brushes, hose equipment, tank trucks, water distributors
131		and flushers, power sweepers, and power blowers.
132		(A) = 1
133		(6) Equipment Calibration. Calibrate in the Engineer's
134		presence all equipment to be used in performance of the work.
135		Submittal of previous calibration documents may be used in lieu of
136		calibration in the Engineer's presence if documented calibration

137

138

139

were made within one calendar year of submittal. Include individual

calibration of each material at various settings, which can be

related to machine's metering devices. No machine will be allowed

to be used on project until calibration has been completed and accepted.

After calibration and prior to production, make test strips for each machine. Test strips shall be part of test section specified in Subsection 404.03(A) - Test Section. Upon failure of test for mix consistency, proportioning, or rate of application, or combination thereof, additional test strips at no increase in contract price or contract time will be required until each machine is accepted for work. Machine failing to pass specified tests after three trials will not be allowed to be used on project.

(E) Preparation of Surfaces. Immediately before applying slurry seal, clean existing pavement in accordance with Section 310 - Brooming Off.

Remove all pavement markers and eradicate the existing thermoplastic pavement striping.

Cold plane the existing pavement to provide a smooth transition between the slurry seal and any existing pavement or structure. The cold planed or ground transition shall be a minimum width of one foot from the edge of the existing pavement or structure and deep enough for the slurry seal to match the grades of the existing pavement or structure.

Distressed areas on the existing pavement indicated for removal and replacement with hot-mix asphalt shall be completed at least seven days prior to the start of slurry seal placement. The reconstructed areas shall not be higher than the existing pavement surface and may be recessed up to 1/8-inch below the existing pavement surface. This work shall be completed and paid for under the pay item, Reconstruction of Weakened Pavement Areas.

Contaminated areas on the existing pavement including but not limited to chemical spills/stains and accumulation of debris or organic matter shall be removed, cleaned with an approved biodegradable cleaning solution, and thoroughly rinsed. Persistent stains shall be removed by spot-grinding or torching and sealed with an approved oil spot primer. High pressure washing is not permitted.

Manholes, valve boxes, drop inlets and other service entrances as well as survey and centerline monuments, shall be protected from the slurry seal by a suitable method. Contractors shall be held liable for any service entrances and monuments covered up resulting from construction. The clean up of any service entrances and monuments shall be at the expense of the contractor.

The Engineer shall approve surface prior to application of slurry surfacing.

(F) Application of Slurry Seal. Apply slurry seal in accordance with ASTM D 3910, ISSA A105, and as indicated in the contract documents. Pour slurry seal into spreader box in sufficient quantity to completely cover full width of spreader. Do not overload the spreader or allow slurry seal to flow out of the sides of the spreader box. The slurry seal shall possess sufficient stability so that the premature breaking of the material in the spreader box does not occur. The mixture shall be homogeneous during and following mixing and spreading. It shall be free of excess water and emulsion and free of segregation of the emulsion and aggregate fines from the coarser aggregate. Spraying of additional water into the spreader box will not be permitted.

Apply slurry seal in one uniformly blended coat. Use hand spreaders only in areas where spreader box cannot be used.

Lumping, balling, or unmixed aggregate in the slurry seal shall not be permitted. No streaks, such as those caused by oversized aggregate, shall be left in the finished surface. If excess oversize develops, the job will be stopped until the Contractor is able to prove that the situation has been corrected. All cost and time expense related to the stoppage will be the responsibility of the Contractor.

The paved surface shall be rolled by a self-propelled, 10-ton vibratory pneumatic roller with a tire pressure of 50 psi, equipped with a water spray system. The surfaced areas shall be subjected to a minimum of two (2) full coverage passes by the roller. Rolling shall not commence until the slurry has cured enough so that it will not pick up on the tires of the roller.

(G) Joints, Trimming Edges, Removal of Excess Material, and Corrective Measures. Excess buildup, uncovered areas, or unsightly appearance shall not be permitted. All excess slurry seal build-up on longitudinal and transverse joints shall be removed. Place longitudinal joints on lane lines. Half passes and odd-width passes may only be used in minimum amounts and only when authorized by the Engineer. The contractor shall provide suitable width-spreading equipment to minimize the number of longitudinal joints throughout the project. Longitudinal lane line joints shall not overlap more than six inches.

Excess slurry seal on areas such as shoulders, gutters, curbs, utility covers, and pavement markers and striping to remain shall be removed.

All deficiencies in the slurry seal, resulting from but not limited to

233	control measures, and early opening to vehicular traffic, shall be repaired
235	before acceptance. All corrective measures shall be considered incidental
236	to the slurry seal. The corrective methods shall be approved by the
237	Engineer.
238	
239	(H) Protection of Slurry Seal. Except for construction equipment used
240	for slurry seal operations, keep traffic off slurry seal until such time that
241	mixture has cured sufficiently so that slurry seal will not adhere to and be
242	picked up by vehicle tires. Ensure that cured slurry seal adheres firmly to
243	existing surface.
244	
245	Measurement. The Engineer will measure slurry seal per square
246	yard in accordance with the contract documents.
247	
248	The Engineer will not measure preparation of surfaces except for distressed
249	asphalt reconstruction work. All other work mentioned in the preparation of
250	surfaces shall be considered incidental to slurry seal activities.
251	
252	404.05 Payment. The Engineer will pay for the accepted slurry seal at the
253	contract unit price basis, as shown in the proposal schedule. Payment will be full
254	compensation for the work prescribed in this section and the contract documents.
255256	The Engineer will pay for the following pay item when included in the
257	proposal schedule:
258	proposal soliculie.
259	Pay Item Pay Unit
260	r uy nom
261	Slurry Seal Square Yard
262	
263	Engineer will pay 100 percent of the contract bid price upon completion of
264	the slurry seal installation."
265	
266	END OF SECTION 404