

1 **SECTION 630 – TRAFFIC CONTROL GUIDE SIGNS**

2
3 Make the following amendment to said Section:

4
5 **(I) Amend Section 630.02 Materials**, by replacing lines 28 to 29 to read:

6
7 “Retroreflective sheeting shall conform to criteria listed in ASTM D 4956
8 for the applicable type and class, or as amended in accordance with Subsection
9 750.01 - Signs.”

10
11 **(II) Amend Subsection 630.04 – Measurement** from lines 204 to 221 to read as
12 follows:

13
14 **“630.04 Measurement.**

15
16 **(A)**The Engineer will measure street name sign, and route marker assembly
17 per each in accordance with the contract documents.

18
19 **(B)** The Engineer will measure panel for destination sign per square foot in
20 accordance with the contract documents.

21
22 **(C)** The Engineer will measure type A route marker assembly, street name
23 sign, 2.50 inch galvanized square tube and flanged channel for destination
24 sign per each in accordance with the contract documents.

25
26 **(III) Amend Subsection 630.05 – Payment** from lines 223 to 296 to read as
27 follows:

28
29 **“630.05 Payment.** The Engineer will pay for the accepted pay items listed
30 below at contract price per pay unit, as shown in the proposal schedule. Payment
31 will be full compensation for the work prescribed in this section and the contract
32 documents.

33
34 The Engineer will pay for the following pay items when included in the
35 proposal schedule:

36

Pay Item	Pay Unit
Panel for _____	Square Foot
Type _____ Route Marker Assembly	Each
Street Name Sign	Each
2.50 Inch Galvanized Square Tube	Each
4.00 lbs./ft. Flanged Channel for Destination Sign	Each

37
38
39
40
41
42
43
44
45
46
47

48 When the Engineer accepts an alternate design, the total amount paid
49 shall be full compensation for furnishing and installing materials and furnishing
50 equipment, tools, labors, and incidentals necessary to complete the work. The
51 Engineer will not make payment for additional materials, equipment, tools, labor
52 and other incidentals that might become necessary to complete the installation
53 due to the alternate design.”
54
55
56

57 **END OF SECTION 630**