

1                   **SECTION 717 – CULLET AND CULLET-MADE MATERIALS**

2  
3       Make the following amendments to said Section:

4  
5       **(I) Amend Subsection 717.01 – Cullet and Cullet-Aggregate Mixtures as**  
6       **Construction Materials** by revising the third paragraph from line 16 to 20 to

7       read:  
8  
9       “Debris shall not exceed values specified in Tables 717.02-1 - Cullet in  
10      Roadway Applications, 717.03-1 - Cullet in Utility Applications, and 717.04-1 -  
11      Cullet in Drainage Applications. Debris is defined as deleterious material that  
12      includes plastics, papers, and non-ceramic constituents of cullet. Hazardous  
13      material will not be allowed in cullet such as but not limited to, TV or other  
14      cathode ray tubes, fluorescent light bulbs, and any toxic or hazardous materials.  
15      Test cullet stockpile for toxic or hazardous materials every 90 days and submit  
16      the results to the Engineer.”

17  
18      **(II) Amend Subsection 717.01 – Cullet and Cullet-Aggregate Mixtures as**  
19      **Construction Materials** by adding the following paragraph after line 21:

20  
21           “Cullet shall not be used in concrete.”

22  
23      **(III) Amend Table 717.03-1 – Cullet in Utility Applications** from line 37 to  
24      line 39 to read:

25

| TABLE 717.03-1 - CULLET IN UTILITY APPLICATIONS  |                                            |                                                    |
|--------------------------------------------------|--------------------------------------------|----------------------------------------------------|
| Utility Trench Bedding and Backfill Applications | Maximum Cullet Content (Percent By Weight) | Maximum Debris Level (Percent By Weight Of Cullet) |
| Sewer Pipes                                      | 25                                         | 0.3                                                |
| Electrical Conduits                              | 25                                         | 0.3                                                |
| Fiber Optic Lines                                | 25                                         | 0.3                                                |

(IV) Amend **Table 717.04-1 – Cullet in Drainage Applications** from line 47 to line 49 to read:

| <b>TABLE 717.04-1 - CULLET IN DRAINAGE APPLICATIONS</b> |                                                       |                                                                   |
|---------------------------------------------------------|-------------------------------------------------------|-------------------------------------------------------------------|
| <b>Drainage Fill Applications</b>                       | <b>Maximum Cullet Content<br/>(Percent By Weight)</b> | <b>Maximum Debris Level<br/>(Percent By Weight Of<br/>Cullet)</b> |
| Retaining Walls                                         | 25                                                    | 0.2                                                               |
| Foundation Drains                                       | 25                                                    | 0.2                                                               |
| Drainage Blankets                                       | 25                                                    | 0.2                                                               |
| French Drains                                           | 25                                                    | 0.2                                                               |

**END OF SECTION 717**