

Amend **Section 615 - Leveling Surfaces** to read as follows:

"SECTION 208 - LEVELING SURFACES

208.01 Description. This work includes removing irregularities in the natural ground surface within or immediately next to the highway right-of-way. Work done under this section shall be exclusive of the clearing, grubbing and final clean-up operations required in other parts of this contract.

208.02 Materials. None specified.

208.03 Construction Requirements. The areas to be leveled or flattened shall be as specified in the Plans or as specified by the Engineer. Remove irregularities in the natural ground surface of the designated areas. Use a power-propelled, pneumatic-tired motor grader. Supplement by hand labor where required. The surface to be leveled or flattened shall provide a surface over which a person may operate the power mowers.

208.04 Method of Measurement. The Engineer will measure the leveling surfaces on a force account basis according to Subsection 109.04 – Extra and Force Account Work and as ordered by the Engineer.

208.05 Basis of Payment. The Engineer will pay for the accepted leveling surfaces on a force account basis according to Subsection 109.04 – Extra and Force Account Work.

The Engineer will make payment under:

Pay Item	Pay Unit
Leveling Surfaces	Force Account"

END OF SECTION