

Amend **Section 310 - Brooming Off** to read as follows:

"SECTION 310 - BROOMING OFF

310.01 Description. This work includes cleaning an existing surface or a pavement according to the contract.

310.02 Materials. None specified.

310.03 Construction Requirements. Remove earth, dust or other foreign material and existing raised pavement markers from the entire area in question. Remove raveled materials from pockets in the surface. Remove the grass or other growth from edges of the area. Crop the adjacent growth closely to prevent interference with subsequent operations. Dispose of debris resulting from the cleaning operations.

Clean the edges of the existing surface so that their original thickness and width may be reconstructed.

Remove loose material and excess dust by mechanically operated broom or air pressure, supplemented by hand brooming where required. Apply air pressure through pipe nozzles operating from a compressor producing 100 psi pressure. Do this work while the surface is thoroughly dry.

310.04 Method of Measurement. The Engineer will not measure brooming off for payment.

310.05 Basis of Payment. The Engineer will not pay for brooming off separately. The Engineer will consider the cost for brooming off as included in the contract price of the various contract items.

The cost is for cleaning an existing surface or pavement according to the contract; and furnishing materials, labor, tools, equipment, and incidentals necessary to complete the work."

END OF SECTION