

SECTION 503 - CONCRETE STRUCTURES

Make the following amendments to said Section:

(I) Amend **503.04 Method of Measurement** to read as follows:

"503.04 Method of Measurement. The Engineer will not measure concrete for payment.

The Engineer will not make deductions for the volume occupied by the reinforcing steel, piles, floor drains, weepholes, timber bumpers, pipes less than 8 inches, conduits, or expansion joint materials.

The Engineer will consider the wingwalls to be a part of the structure.

The Engineer will measure reinforcing steel according to Section 602 – Reinforcing Steel.

(II) Amend **503.05 Basis of Payment** to read as follows:

"503.05 Basis of Payment. The Engineer will pay for the accepted concrete on a contract lump sum basis complete in place.

The price includes full compensation for the concrete; for placing, curing and finishing; for furnishing materials including admixtures and cement (including extra cement added to concrete deposited under water); for furnishing and installing drains, scuppers, premolded joint fillers, joint seals, waterproofing at construction joints, waterstops, pipes, and conduits; for furnishing and installing metal rockers, anchor bolts, structural shapes for expansion joints and other similar items; for timber bumpers, forms, form lining and falsework or centering, bearing pads, structural steel bearing plates; and for equipments, tools, labor, materials, and incidentals necessary to complete the work.

The Engineer will make payment under:

Pay Item	Pay Unit
Concrete _____	Lump Sum
Type B Wall	Lump Sum

The Engineer will pay for reinforcing steel for Type "B" Wall according to Section 602 – Reinforcing Steel. The Engineer will not pay for reinforcing steel for Concrete Headwall."

END OF SECTION