

## **SECTION 702 - BITUMINOUS MATERIAL**

Make the following amendments to said Section:

(I) Amend 702.01 **Asphalt Cement** to read as follows:

**"702.01 Asphalt Cement.** Performance graded asphalt binder shall conform to AASHTO M 320. "

(Table deleted.)

(II) Amend 702.04 **Emulsified Asphalts** to read as follows:

**"702.04 Emulsified Asphalt.** Anionic emulsified asphalt shall conform to AASHTO M 140, except that the penetration on residue for Type SS-1 and Type RS-1 shall be 50-120 in lieu of the 100-200 specified.

Cationic emulsified asphalt shall conform to AASHTO M 208, except that the penetration on residue for Type CSS-1 and Type CRS-2 shall be 50-150 in lieu of the 100-250 specified."

**END OF SECTION**