

General Notes:

1. The Contractor shall obtain a construction permit from the State's Highway District Engineer at 3060 Eiuva Street, Lihue, Kauai prior to commencement of work within State highway right-of-way.
2. Construction and restoration of all existing highway facilities within State right-of-way shall be done in accordance with applicable sections of the current Standard Specifications for Road and Bridge Construction, and the Specification for Installation of Miscellaneous Improvements Within State Highways, of the State Highways Division.
3. All lanes shall be opened to traffic during the morning peak hours from 6:30 A.M. to 8:30 A.M., and during the afternoon peak hours from 3:30 P.M. to 5:30 P.M., and during off-work hours. Only one lane of traffic shall be closed at any other time.
4. The Contractor shall provide, install, and maintain all necessary signs, lights, flares, barricades, markers, cones, and other protective facilities and shall take all necessary precautions for the protection and for the convenience and safety of public traffic. All such protective facilities and precautions to be taken shall conform with the "Administrative Rules of Hawaii Governing the Use of Traffic Control Devices at Work Sites on or Adjacent to Public Streets and Highways" adopted by the Director of Transportation, and the current U.S. Federal Highway Administration "Manual on Uniform Traffic Control Devices for Streets and Highways, Part VI - Traffic Control for Highway Construction and Maintenance Operations". If lane closures are required during construction, a traffic control plan shall be incorporated into the construction plans and must be approved by the Division prior to the issuance of the permit.
5. No material and/or equipment shall be stockpiled or otherwise stored within highway rights-of-way except at locations designated in writing and approved by the District Engineer.
6. The Contractor shall be required to provide adequate, safe, non-skid bridging material over the trench, including shoring, when trenching in pavement areas to handle all types of vehicular traffic.
7. All regulatory, guide and construction signs and barricades shall be of high intensity reflective sheeting.

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	56C-01-93M	1993	2	7

DATE	_____
SURVEY PLOTTED BY	_____
DRAWN BY	_____
TRACED BY	_____
DESIGNED BY	_____
QUANTITIES BY	_____
CHECKED BY	_____
ORIGINAL PLAN	_____
NOTE BOOK	_____
NO.	_____

STATE OF HAWAII	
DEPARTMENT OF TRANSPORTATION	
HIGHWAYS DIVISION	
GENERAL NOTES	
KUHIO HIGHWAY	
STORM DAMAGE RECONSTRUCTION	
VICINITY OF M.P. 13.9 OUTBOUND	
PROJECT NO. 56C-01-93M	
Scale: None	Dec. 1992
SHEET NO. 2 OF 7 SHEETS	