FED. ROAD	STATE	FED. AID	FISCAL	SHEET	TOTAL
DIST. NO.		PROJ. NO.	YEAR	NO.	SHEETS
HAWAII	HAW.	56A-02-93	1994	15	15

PAVEMENT MARKING SUMMARY	
DESCRIPTION	QUANTITY
PAVEMENT MARKERS TYPE A TYPE C TYPE D	80 EA. 64 EA. 32 EA.
TAPE - TYPE I OR THERMOPLASTIC EXTRUSION 8-INCH PAVEMENT STRIPE (WHITE) DOUBLE 4-INCH PAVEMENT STRIPE (YELLOW)	400 L.F. 620 L.F.
TAPE - TYPE II OR THERMOPLASTIC EXTRUSION 4-INCH PAVEMENT STRIPE (WHITE)	1,100 L.F.
TAPE - TYPE III OR THERMOPLASTIC EXTRUSION 4-INCH PAVEMENT STRIPE (YELLOW) 12-INCH PAVEMENT STRIPE (WHITE) CROSSWALK MARKINGS PAVEMENT ARROW	120 L.F. 70 L.F. 8 LANES 10 EA.

TRAFFIC SIGN SUMMARY						
		QUANTITY				
SIGN NO.	MESSAGE	10 SQ. FT. OR LESS		GREATER THAN 10 SQ. FT.		
		W/POST	W/O POST	W/POST	W/O POST	
R3-28	N I P ONLY	2				
R10-12	LEFT TURN YIELD ON GREEN	1	1			
	TOTAL	3	1	0	0	

	CONSTR	UCTION SIGN SUMMARY		
SIGN NO.	LOCATION	MESSAGE	W/POST	W/O POST
CW20-1d	Kuhio Hwy Sta. 100+50 Rt.	Road Construction Ahead	1	
CW20-1d	Kuhio Hwy Sta. 115+50 Lt.	Road Construction Ahead	1	
CW20-1d	Poinciana St. Sta. 3+00 Lt.	Road Construction Ahead	1	
CG20-2	Kuhio Hwy Sta. 100+50 Lt.	End Construction	1	
CG20-2	Kuhio Hwy Sta. 115+50 Rt.	End Construction	1	
CG20-2	Poinciana St. Sta. 3+00 Rt.	End Construction	1	
		TOTAL	6	0

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TRAFFIC SUMMARIES

Kuhio Highway Traffic Signals

At Poinciana Street

Project No. 56A-02-93

Date: March, 1994

SHEET No. 77 OF 7 SHEETS

 ORIGINAL
 SURVEY PLOTTED BY
 DATE

 PLAN
 DRAWN BY X
 X

 IOTE BOOK
 DESIGNED BY X
 .

 #OLAUby
 QUANTITIES BY
 .

 CHECKED BY
 .
 .